

SURVEY & REMONUMENTATION

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
Ottawa

Located in:	Corner Code #
Blendon Twp. 6N R 14W	I-10, E 1/4 cor. Sec. 27
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
T ___ R ___	_____
2. Property Controlling in Section S ___ T ___ R ___	_____
S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec. S ___ T ___ R ___	_____
S ___ T ___ R ___	_____

RECORDED

95 NOV 29 PM 1:38

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Randal D. Feenstra November 6 95

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1832) Calvin Britain 6" Pine N78E 4 lks. 3" Pine S66E 33 lks.	LIBER 2, PAGE 259 (1973) 1" Bar 30" Ash SW 33.34' St. Sign E 17.89' 24" Oak SSW 122.28' 4" Ash NE 33.68'	LIBER 2, PAGE 541 (1974) 1" Iron Spike in 24" Ash WSW 33.30' Spike in 4" Twin Oak ESE 65.21' RR spike in 24" Ash NNW 70.37'	LIBER 4, PAGE 350 (1982) C.I.M. 24" Ash WSW 33.30' 26" Ash NW 70.37' 12" Poplar NE 28.51' St. Sign E 18.2'
--	---	---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found: C.I.M. Accepted as a careful and faithful perpetuation of the position of the original corner.
Nail in S side 28" Ash WSW 33.34'
Nail in SW side 30" Ash NW 70.10'

RA. 345 OTTAWA COUNTY
PEER APPROVED 11/20/95

Randal D. Feenstra
RDF

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10	C.I.M. in gravel		
	Ottawa County Remon. Nail & Tag in S. side 28" Ash	245°	33.39'
	Ottawa County Remon. Nail & Tag in SW side 30" Ash	335°	70.18'
	Ottawa County Remon. Nail & Tag in NW side 26" Poplar	50°	27.90'
	Ottawa County Remon. Nail & Tag in SW side P. Pole	130°	46.70'

2' S and 4' W of centerline "X" 64th Ave. and Bingham



Signed by Randal D. Feenstra Date November 6, 1995
Surveyor's Michigan License No. 37275