

SURVEY & REMONUMENTATION

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in
Ottawa
(County)

Located in: Blendon Twp. Corner Code # J-9, N 1/4 cor.

1. Public Land Survey	T	<u>6N</u>	R	<u>14W</u>	<u>Sec. 26</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

RECORDED
95 NOV 29 PM 1:37
Phyllis Redman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	N
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal D. Feenstra in a field survey on November 6, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1832) Calvin Britain 30" W Oak S 4 lbs. 36" W Oak N54°W 24 lbs.	L-1, P-409, 1972 Iron In Mon. P. Pole St. Sign T. Pole	NE 50.91' SE 38.00' SE 46.13'	L-1, P-759, 1972 Iron 26" Oak P. Pole	NNE 116.0 NE 50.05'	L-2, P-57, 1973 Iron in Mon. Box (No Witnesses)
--	--	-------------------------------------	--	------------------------	---

L-5, P-121, 1984
C.I.M.
St. Sign SE 36.88'
P. Pole NE 51.27'
T. Pole SW 46.22'
Nail in Guard Post NW 33.40'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found : C.I.M. in box Accepted as a careful and faithful perpetuation of the position of the original corner.

St. Sign SE 36.31'
Nail in SE side P. Pole NE 51.20'
Nail in SE side cut-off P. Pole SW 46.14'


PEER APPROVED 11/20/95

Peer Approved Signature

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9	C.I.M. in Box		
	Ottawa County Remon Nail & Tag in SE side P. Pole	40°	51.21'
	Ottawa County Remon Nail & Tag in W side 30" Oak	9°	116.90'
	SE Cor. Fndn. of Hse. # 6019	315°	111.11'
	NE Cor. Fndn. of Barn	222°	134.39'

On centerline of Port Sheldon and 5' E of centerline 60th Ave



Signed by Randal D. Feenstra

Date November 6, 1995

Surveyor's Michigan License No. 37275