

SURVEY & REMONUMENTATION

NOV 10 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
OTTAWA COUNTY REMONUMENTATION

For corners in
OTTAWA
 (County)

Located In: BLENDON TWP. Corner Code #

1. Public Land Survey	T 6N R 14W	L-9, S $\frac{1}{4}$ Cor-24
	T 6N R 14W	M-9, SE Cor-24
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECORDED

393 SEP 29 PM 3:13

Ryland D. Feenstra
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Randal D. Feenstra in a field survey on July 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- L-9 = LCRC#'s L-3, P-161; L-5, P120
- M-9 = LCRC#'s L-3, P-161; L-5, P-126

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- | | |
|---|---|
| L-9 | M-9 |
| Found Cast Iron Monument in Box
And Witnesses Per
LCRC # L-5, P-120 | Found Cast Iron Monument in Box
And Witnesses Per
LCRC # L-5, P-126 |



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-9-Cast Iron Monument per L-5, P-120, Ottawa County, MI, and is accepted as a careful and faithful perpetuation of the position of the original corner.
 - O.C. Remon. Nail & Tag in Power Pole N8°W 35.26
 - O.C. Remon. Nail & Tag in Power Pole S0°E 45.92
 - O.C. Remon. Nail & Tag in 34" Maple N27°W 48.77
 - O.C. Remon. Nail & Tag in 26" Maple S30°E 82.91
- ⓐ CL Port Sheldon
 - M-9-Cast Iron Monument per L-5, P-126, Ottawa County, MI, and is accepted as a careful and faithful perpetuation of the position of the original corner
 - O.C. Remon. Nail & Tag in Power Pole S42°E 60.53
 - O.C. Remon. Nail & Tag in Telephone P. N44°E 43.31
 - O.C. Remon. Nail & Tag in Light Pole N50°W 53.64
 - Georgetown Twp cor (Mon. in box) S0°E 12.54
 - CL "X" Port Sheldon & 48th

Signed by Randal D. Feenstra Date July 13, 1993
 Surveyor's Michigan License No. 37275