

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

96 DEC 18 PM 4: 55

For corners in
Ottawa

Located In: Corner Code #

	(County)	Blendon Twp.	
1. Public Land Survey	T <u>6</u> N	R <u>14</u> W	M-10, E 1/4 cor. Sec. 25
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

Ralphie Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randal D. Feenstra, in a field survey on July 6, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. (1831)
Lucius Lyons Post
18" Maple N31°W 12 lks.
6" Beech S22°W 35 lks

P.A. 345 OTTAWA COUNTY
PLER APPROVED 12-9-96

R.D.F.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10 Found: Cast Iron Monument in Box - Unrecorded
Accepted as a careful and faithful perpetuation of the position of the original corner.

(See sketch on back)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-10 Cast iron Monument in Box (SEE SKETCH ON BACK)
Ottawa County Remon Nail & Tag in 8" Poplar S75°E 44.05'
Ottawa County Remon Nail & Tag in P. Pole S12°E 125.69'
Ottawa County Remon Nail & Tag in P. Pole S50°W 71.47'
Ottawa County Remon Nail & Tag in Twin 6" Birch N25°W 58.83'

W 1/4 Cor., Sec. 30 of Georgetown Township - S0°E 10.24'
On CL 48th Ave., Treeline E & W S S.



Signed by *Randal D. Feenstra*
Surveyor's Michigan License No. 37275

Date July 15, 1996

