

SURVEY & RECONSTRUCTION

FEB 18 1994

OTTAWA COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV -8 PM 1:58

D. J. ...
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in COMMISSION

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>14W</u>	M-12, E1/4 COR. Sec. 36, Btendon
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Randal D. Feenstra, in a field survey on Sept. 27, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 L-3, P-115 Boat Spike	L-5, P-127 Cast Iron Monument
Spike in 48" maple SE 45.38'	48" maple SE 45.30'
NW cor. house ESE 57.73	P. Pole SW 65.50'
"T" iron(Geo. Cor) N 11.22'	Georgetown Cor. N 11.25'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found Cast Iron Monument - accepted as a careful and faithful perpetuation of the position of the original corner.
 Found Georgetown Cor. N. 11.45'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Set O.C. Remon. Rod and Cap in concrete
O.C. Remon. Nail & Tag in P. Pole S40°W 73.74'
O.C. Remon. Nail & Tag in New P.Pole S20°E 68.06'
O.C. Remon. Nail & Tag in Twin 30" Maple N70°W 125.14'
SE Cor, Garage Fnd'n N40°W 96.62'
Georgetown Corner N0°E 11.45'
On CL 48th



Signed by Randal D. Feenstra Date Sept 29, 1993

Surveyor's Michigan License No. 37275