

**SURVEY & REMONUMENTATION**

DEC 01 1998

RECORDED

SECTION

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE** 88 MAY 22 PM 4:06  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>15W</u>	<u>A-13</u> (SW, 13)
	T _____ R _____	Olive Twp.
	T _____ R _____	<del>COMMON CORNER</del>
	T <u>5N</u> R <u>15W</u>	<u>A-1</u>
2. Property Controlling in Section	S _____ T <u>6N</u> R <u>16W</u>	<u>M-13</u>
	S _____ T <u>5N</u> R <u>16W</u>	<u>M-1</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Ray [Signature]*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John C. Bueche, in a field survey on March 26, 19 98, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-13 GLO	LCRC Remon. L1, P452 (recorded as M-13, 6-13)
Calvin Britain, 1832	Found Ottawa Co. Cast Iron Mon.
Post	Ottawa Co. Remon. Tag & Nail in W face PP Az 358° 164.92'
10" Tamarack N 47 W 110	C/L hydt. Az 29 34.41'
8" Pine N 88 E 93	Ottawa Co. Remon. Tag & Nail in W face PP Az 178° 52.03'
	C/L 144th Ave. Az 90° 86'±
	Ottawa Co. Remon. Tag & Nail in N face PP Az 105° 121.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-13 Found Ottawa Co. Cast Iron Mon. 1'± below grade  
 On C/L bit. E-W; C/L bit. N-S is East 86'±  
 As per above wit.

And is accepted as a careful and faithful perpetuation of the position of the original corner.

PA. 345 OTTAWA COUNTY  
 PEER APPROVED 4/20/98

*[Signature]*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13 Ottawa Co. Cast Iron Mon. in Mon. Box  
 Ottawa Co. Remon. Tag & Nail in W face PP Az 358° 164.92'  
 C/L hydt. Az 29 34.41'  
 Ottawa Co. Remon. Tag & Nail in W face PP Az 178° 52.03'  
 Ottawa Co. Remon. Tag & Nail in N face PP Az 105° 121.50'  
 Mon. Box East 86'±  
 On C/L bit. E-W; C/L bit. N-S East 86'±



\$ 9.00 CORNER  
 \$ 1.00 PHOTO

Signed by John C. Bueche Date 4-1-98  
 John C. Bueche, P.S. 13027  
 Surveyor's Michigan License No. \_\_\_\_\_