

**SURVEY &  
REMONUMENTATION**

**FEB 27 1998**

**SECTION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

**RECORDED  
97 OCT 30 AM 10:59**

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

<u>Ottawa</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>15W</u>	<u>B-3</u>
	T _____ R _____	(N 1/4 cor., Sec. 7
	T _____ R _____	Olive Twp.)
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Debra Gant*

**Register of Deeds  
Ottawa County, MI**

Register of Deeds Stamp & File Number

I, Douglas J. Koning, in a field survey on September 3, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**A. Description of original monument and accessories and/or subsequent restoration:**

B-3 Government Notes	L.C.R.C. Liber 2, Page 571, September 1974
Set Post May 1832	Set Cast Iron Monument
By Calvin Britain D.S.	Triple 14" Oak NW 55.22'
Hemlock 3" S51'E 20 Links	Triple 16" Oak W 61.92'
Beech 15" N78'E 7 Links	Twin 8" Oak S 62.03'
	Twin 14" Oak SE 28.18'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.**

B-3 Found Cast Iron Mon (top broken)  
Found Nail & Tag in face of 18" Twin Oak S19'E 28.15'  
Found Nail & Tag in face of 14" Twin Oak S 62.01'

**RA: 845 OTTAWA COUNTY**  
**PEER APPROVED** 10/27/97  
*[Signature]*

This marker is accepted as a careful and faithful perpetuation of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

B-3 Found Cast Iron Mon (top broken)  
Set Ottawa County Remon Nail & Tag in NE side 18" Twin Oak S21'E 28.60'  
Set Ottawa County Remon Nail & Tag in W side 14" Twin Oak South 62.40'  
Set 1/2"x18" Iron Rods Cap #35995 North 50.0' & 100.0' (not on Section line)  
Set 1/2"x18" Iron Rods Cap #35995 East 50.0' & 100.0' (not on Section line)

\* 9.00 CORNER  
\* 1.00 PHOTO

Signed by Douglas J. Koning Date 10-27-97  
Surveyor's Michigan License No. 35995

