

SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

94 DEC -8 PM 12:36

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

Daphne Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

<u>Ottawa</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T 6N R 15W	C-8	
	T _____ R _____	(W 1/4 cor., Sec.	
	T _____ R _____	20, Olive Twp.)	
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Douglas J. Koning, in a field survey on August 17, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/of subsequent restoration:

C-8 Government Notes	L.C.R.C. Liber 1, Page 343 April 1972
Set Post May 1832	C-8 Set Cast Iron Monument inscribe
By Calvin Britain D.S.	"Ottawa County Section Corner" from old County ties
Hemlock 4" S16°W 18 Links	Nail in face 16" Spruce N24°E 38.94'
Leo 3" N45°W 9 Links	Nail in face 12" Spruce NE 54.60'
	Nail in face Tel. Pole SW 41.74'
	Nail in face Pwr Pole SE 111.66'
	S End Bridge Railing N55°W 14.15'
	NE Corner Att. Garage SW 130.01'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

C-8 Found Cast Iron Monument	
Nail in face 16" Spruce	N24°E 38.87'
Nail in face 12" Spruce	NE 54.56'
Nail & Tag in face Pwr Pole	SE 111.57'
NE Corner Att. Garage	SW 130.0'±

PA. 345 OTTAWA COUNTY


PEER APPROVED 11/21/94

Kendry D. Hedewell

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

C-8 Cast Iron Monument (12' N of centerline "X" of Roads)	
O.C. Remon Tag & Nail SE Side 12" Spruce	N60°E 55.46'
O.C. Remon Tag & Nail SW Side Pwr Pole	S67°E 111.77'
O.C. Remon Tag & Nail Nly Side Twin 16" Basswood	S78°W 115.41'
NE Cor. Brick House	S43°W 144.60'



Signed by Douglas J. Koning
Surveyor's Michigan License No. 35995

Date November 14, 1994