

**SURVEY &
REMONUMENTATION**

APR 05 1996

**COMMISSION OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

RECORDED

95 DEC 12 PM 1:51

For corners in Ottawa (County) Located in: _____ Corner Code # _____
Filing Requirement of Act 74, Mich. P.A. 1970

Douglas J. Koning
REGISTER OF DEEDS
OTTAWA COUNTY, MI

- | | | |
|---------------------------------------|---------------------------|--|
| 1. Public Land Survey | T <u>6N</u> R <u>R15W</u> | C-13
(SW cor., Sec. 32
Olive Twp.) |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Register of Deeds Stamp & File Number

I, Douglas J. Koning, in a field survey on November 22, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/of subsequent restoration:

- | | | | | |
|--|---|---|---|---|
| C-13 Government Notes
Set Post May 1832
Black Ash 10" N80°E 11 Links
Hemlock 10" N16°W 5 Links
Calvin Britain D.S. | L.C.R.C. Liber 1, Page 515 July 1972
C-13 Iron Pipe
Nail in face of Power Pole SSW 43.97'
Nail in face of Telephone Pole NNW 64.39'
Centerline hydrant ESE 91.18'
Centerline Road E 31.60' | L.C.R.C. Liber 3, Page 280 Aug. 1978
C-13 Iron Pipe
Power Pole SSW 43.97'
Telephone Pole NNW 64.34'
Centerline hydrant ESE 93.96'
Centerline Road E 32.50'
Cast Iron Monument N88°E 67.13'
(Holland Township Corner) | L.C.R.C. Liber 3, Page 321 Jan. 1979
C-13 Found Iron Pipe
Power Pole SSW 43.97'
Telephone Pole NNW 64.34'
Centerline hydrant ESE 93.96'
Centerline Road E 32.50' | L.C.R.C. Liber 3, Page 365 July 1979
C-13 Iron Pipe
Power Pole SSW 43.97'
Telephone Pole NNW 64.34'
Centerline hydrant ESE 93.96'
Centerline Road E 32.50'
Cast Iron Monument N88°E 67.13'
(Holland Township Corner) |
|--|---|---|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

- | |
|---|
| C-13 Found Cast Iron Monument at surface of Gravel Road
Found Nail & Tag (T.K.&A.) in face P.P. SSW 43.92'
Centerline Hydrant ESE 94.07'
Found Nail SE side Guy Pole NE 72.35'
Found Cast Iron Monument in Box N88°E 67.12' |
|---|

P.A. 345 OTTAWA COUNTY


PEER APPROVED 12/11/95

Bedoy P. Nedewell

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- | |
|--|
| C-13 Cast Iron Monument (32' E of Centerline "X" & 4' S)
Set Remon Tag & Nail in W side Power Pole S20°W 44.27'
Set Remon Tag & Nail in SE side Guy Pole N65°E 72.16'
Set Remon Tag & Nail in S side Power Pole N80°E 129.39'
Set Remon Tag & Nail in S side Power Pole S70°E 139.05'
Set Remon Tag & Nail in N side Power Pole S80°W 135.18' |
|--|



Signed by Douglas J. Koning Date 12-11-95
Surveyor's Michigan License No. 35995