

SURVEY & REMONUMENTATION

OCT 07 1996

COMMISSION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 AUG 26 PM 2:01

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located in:	Corner Code #
1. Public Land Survey	T 6N R15W	E-2
	T _____ R _____	(E 1/4 cor., Sec. 5
	T _____ R _____	Olive Twp.)
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	▲	4	3	2						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

Douglas J. Koning, In a field survey on February 20, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/of subsequent restoration:

E-2 Government Notes	L.C.R.C. Liber 3, Page 207 November 1977
Set Post May 1832	E-2 Cast Iron Monument
By Calvin Britain D.S.	28" Maple NE 35.98'
Beech 12" S38°E 17 Links	24" Maple ESE 51.95'
Leo 10" N58°W 18 Links	Centerline Street Sign SSW 28.00'
	24" Maple NW 36.05'

L.C.R.C. Liber 6, Page 215 April 1992
E-2 Found Cast Iron Monument
26" Maple NE 36.00'
26" Maple NW 48.95'
22" Maple SE 50.78'
34" Maple SW 96.88'

RA 345 OTTAWA COUNTY
PEER APPROVED 8-20-96

Charles D. Pedersen

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.


E-2 Found Cast Iron Monument	
Found Nail & Tag in NW side 26" Maple	NE 35.98'
Found Nail in NE side 26" Maple	NW 48.94'
Found Nail in NE side 22" Maple	SE 50.74'
Found Nail in E side 34" Maple	SW 96.83'
Found PK Nail in NW side 26" Maple	NE 35.84'
Found Nail in face of 26" Maple	NE 34.52'

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

E-2 Cast Iron Monument ± 1.2' Deep	
Set Remon Tag & Nail in E side 36" Maple	S15°W 96.74'
Set Remon Tag & Nail in NE side 26" Maple	S30°E 50.80'
Set Remon Tag & Nail in NW side 30" Maple	N40°E 36.00'
Set Remon Tag & Nail in Sly side 36" Maple	N60°W 48.43'
In Centerline "X" of Roads	

Signed by *Douglas J. Koning*
Surveyor's Michigan License No. 35995



Date 8-20-96

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN. 1983