

**SURVEY & REMONUMENTATION**

APR 05 1996

**COMMISSION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED**

95 NOV 15 PM 2:11

*Phyllis Anderson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in Ottawa (County) Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 6N R 15W E-13  
T \_\_\_\_\_ R \_\_\_\_\_ (SW cor., Sec. 33  
T \_\_\_\_\_ R \_\_\_\_\_ Olive Twp.)  
T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Douglas J. Koning, in a field survey on October 20, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/of subsequent restoration:**

E-13 Government Notes  
Set Post May 1832  
Beech 18" N53°W 13 Links  
Leo 10" N53°E 31 Links  
C. Britain, P.S.  
L.C.R.C. Liber 2, Page 85, March 1973  
E-13 Found "I" Iron  
Centerline Hydrant NE 45.99'  
East to Holland cor. gron. 70.30'

E-1 T5N, R15W  
Government Notes  
1.18' East of Post (77.88')  
L.C.R.C. Liber 3, Page 213, November 1977  
E-13 Set Cast Iron Monument  
Centerline Hydrant NE 45.96'  
24" Maple ESE 103.91'  
Holland corner E 70.3'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.**

E-13 Found Cast Iron Monument in Box  
Centerline Hydrant NE 45.90'  
Cast Iron Monument East 70.24'

**P.A. 345 OTTAWA COUNTY**  
**PEER APPROVED** 10/23/95

*Phyllis Anderson*

This marker is accepted as a careful and faithful perpetuation of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.**

E-13 Cast Iron Monument in Box (2' East and 1' North of Centerline "X" Roads N, E, W)  
Centerline of Hydrant N47°E 45.90'  
Set O.C. Remon Tag & Nail N side 24" Maple S71°E 130.32'  
Set O.C. Remon Tag & Nail W side Power Pole S04°E 284.44'  
Cast Iron Monument in Box East 70.24'  
Cut "X" in N end of Concrete Culvert N78°E 105.42'

Signed by Douglas J. Koning Date 10-20-95  
Surveyor's Michigan License No. 35995

