

FEB 24 2000

RECORDED

99 SEP 23 PM 3:20

SECTION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

OTTAWA

(County)

Located In:

Corner Code #

- 1. Public Land Survey T6N R 15W F-7 N 1/4 corner
- T ___ R ___ Section 21, Olive
- T ___ R ___ Twp _____
- T ___ R ___ _____
- 2. Property Controlling S ___ T ___ R ___ _____
- in Section S ___ T ___ R ___ _____
- 3. Miscellaneous S ___ T ___ R ___ _____
- Property in Sec. S ___ T ___ R ___ _____

Randy Schmitt
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Randal J Vugteveen, in a field survey on September 16, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-7 GLO Calvin Britian
April, 1832
Set post
12" Maple S30°W 10 links
18" Beech N40°E 20 links

F-7 LCRC Liber 1, Page 781 Clapp, October 1972
Set Cast Iron Monument
Telephone Pole NW 50.72'
Power Pole SE 56.02'
Street Sign centerline SW 47.94'
24" Sycamore SW 87.80'
Power Pole SW 57.69'

F-7 LCRC Liber 2, Page 709
Nov., 1974 Fauser
Found 4" iron cap (Ottawa Co. Section Corner)
Power Pole S50°E 56.13'
Telephone Pole S50°W 57.70'
Street Sign post S45°W 48.00'
30" Tree S35°W 87.96'
Intersection of Roads West 16.00'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 June 3, 1999 Found Broken Cast Iron Monument

Found Nail and Remon Tag E side 30" Sycamore 89.22'
Center cut off Telephone Pole S53°W 58.0'
Found Nail in fence Power Pole S37°E 55.97'
Centerline "X" 3' South and 16' West
OCRC is rebuilding road at this time.

Accepted broken Cast Iron Monument as a careful and faithful perpetuation of the position of the original corner
Set iron witness points outside construction area.

September 16, 1999 recovered witness points
Found bottom 12" of Cast Iron Monument.
Bottom of monument checked good with witness control
Removed C.I.Mon
Set 3/4" x 36" solid bar with Remon Cap

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 3/4" x 36" long solid bar with Remon Cap

Set Nail & O.C. Remon Tag SE side P.Pole S37°E 56.45'
Found Nail & O.C. Remon Tag E side 30" Sycamore S27°W 89.19'
Set Nail & O.C. Remon Tag SE side cutoff MBT Pole S53°W 58.07'
Set "X" on top of 54" Conc. Culvert N13°E 34.17'
On Centerline E & W Gravel Road
16' East of Centerline N & S Gravel Road

Randy Schmitt
9/20/99
\$9.00 CORNER
Receipt #50324
RANDALL VUGTEVEEN
NO. 28429
Date SEPT 20, 1999

Signed by *Randy Schmitt*
Surveyor's Michigan License No. 28429