

**SURVEY &
REMONUMENTATION**

DEC 01 1993

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE 93 NOV 11 AM 11:55

Filing Requirement of Act 74, Mich. P.A. 1970

Douglas J. Koning
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>15W</u>	<u>G-6</u>
	T _____ R _____	<u>(W 1/4 corner</u>
	T _____ R _____	<u>of Section 15</u>
	T _____ R _____	<u>Olive Twp.)</u>
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Douglas J. Koning in a field survey on September 8, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L.C.R.C. L. 2 Pg. 155 1973	L.C.R.C. L. 2 Pg. 709 1974	L.C.R.C. L. 6 Pg. 54 1990
G-6 Set R.R. Spike 1/2 Way on line	G-6 Found R.R. Spike on Bridge Deck	G-6
Cut "X" in NW Hdw. Post WNW 10.72'	NE corner bridge 16.17'	Set CIM
Cut "X" in SW Hdw. Post SSW 21.63'	NW corner bridge 10.52'	Nail in E face of Fence Post NW 36.1'
Cut "X" in SE Hdw. Post SSE 25.13'	SW corner bridge 22.13'	"X" in top of N Culvert W 35.1'
Cut "X" in NE Hdw. Post ENE 16.5'	SE corner bridge 25.35'	"X" in Rivet Middle Culvert ESE 35.1'
	Corner is 2.3' W of centerline blacktop	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6 Found C.I.M. in Mon. Box (top busted off) 1/2 way on line		
Nail (Bent) in E. Face of Fence Post	NW	36.81'
"X" in top of N. Culvert	W	35.15'
"X" in Rivet of Middle Culvert	ESE	35.23'

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6 Set O.C. Remon Cap (2.5' W. of centerline bit. road)		
PK Nail and O.C. Remon Tag W. end middle CMP	S72°W	36.83'
PK Nail and O.C. Remon Tag E end North CMP	S86°E	35.05'
Nail and O.C. Remon Tag E. side Wood Fence Post	N49°W	36.95'
Nail and O.C. Remon Tag S'ly side Power Pole	S67°E	84.43'
SW cor. house (Brick Facing)	N36°E	195.85'
Half way on line between G-5 & G-7		

Signed by Douglas J. Koning
Surveyor's Michigan License No. 35995

