

**SURVEY &
REMONUMENTATION**

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

RECORDED

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

95 NOV 15 PM 2:11

<u>Ottawa</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 6N R 15W	G-13
	T _____ R _____	(SW cor., Sec. 34
	T _____ R _____	Olive Twp.)
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Richard C. Caldwell
**REGISTER OF DEEDS
OTTAWA COUNTY, MI**

Register of Deeds Stamp & File Number

I, Douglas J. Koning, in a field survey on October 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/of subsequent restoration:

G-13 Government Notes Set Post May 1832 Beech 20" N43°W 24 Links Leo 10" N31°E 25 Links	L.C.R.C. Liber 1, Page 269, February 1972 G-13 Found Iron Pipe Nail in face of Guy Pole NW 48.25' Nail in face of Pow. pole WSW 116.60' Nail in face of Pow. pole SE 95.55' SW House cor. NE 120.65'
G-1 T5N, R15W Government Notes .78' East of Post (51.48')	

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

G-13 Found Cast Iron Monument in Box SW corner House Foundation	NE 120.72'
Found Nail South Side Power Pole	WSW 117.17'
Found H.E.I. Cap & Nail SW Side Guy Pole	NW 48.86'
Found Cast Iron Monument in Box	East 51.69'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

YD V. Medow P. Medow

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

G-13 Found Cast Iron Monument in Box	S77°W 117.03'
Set O.C. Remon Tag & Nail North Side Power Pole	N56°W 48.72'
Set O.C. Remon Tag & Nail North Side Power Pole	N36°E 120.72'
SW Corner Concrete Block Foundation (House)	N59°E 172.97'
SW Corner Concrete Block Building	S71°W 242.94'
NE Corner Concrete Foundation (North Holland Reformed Church)	East 51.69'
Cast Iron Monument in Box	S73°E 98.81'
Set O.C. Remon Tag & Nail in N. Side Power Pole	

Signed by Douglas J. Koning
Surveyor's Michigan License No. _____

Date 10-20-95

