

**SURVEY &
REMONUMENTATION**

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

<u>Ottawa</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 6N R15W	H-13
	T _____ R _____	(S 1/4 cor., Sec. 34
	T _____ R _____	Olive Twp.)
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

95 NOV 15 PM 2:12

Polystis Bullman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Douglas J. Koning, in a field survey on October 20, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/of subsequent restoration:

H-13 Government Notes	L.C.R.C. Liber 1, Page 585, August 1972
Set Post May 1832	H-13 "I" Iron
Beech 12" N35°W 20 Links	Centerline St. Sign S 26.22'
Sugar 10" N11°E 12 Links	11" Ash SW 64.15'
	Pow. pole NNW 103.24'
	L.C.R.C. Liber 3, Page 213, November 1977
	H-13 Set Cast Iron Monument
	12" Ash WSW 64.8'
	Centerline St. Sign S 26.84'
	Pow. Pole NW 103.8'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

H-13 Found 1/2" Rebar in Box	NW	103.69
Found PK Nail SW Side Power Pole	NW	103.71
Found Nail NE Side Power Pole	South	37.40'
Street sign	SE	104.26'
Found PK Nail W side Power Pole	East	61.92'
Found 1/2" Rebar in Box		

P.A. 345 OTTAWA COUNTY

PEER APPROVED 10/23/95

Keddy D. McDowell
DDW

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

H-13 Set Form Pin and O.C. Remon. Cap		
Set O.C. Remon Tag & Nail NE side Power Pole	N33°W	103.74'
Set O.C. Remon Tag & Nail W side Power Pole	S35°E	104.36'
NE corner Pole Building (Wood Siding)	S11°E	104.77'
NW corner Pole Building (Wood Siding)	S20°W	107.71'
1/2" Rebar in Box	East	61.92'
NE corner Pole Building (Wood Siding)	S58°W	186.06'

Signed by Douglas J. Koning
Surveyor's Michigan License No. _____

Date 10-20-95

