

**SURVEY &  
REMONUMENTATION**

DEC 01 1993

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
93 NOV 11 AM 11:55

*Dorothy R. Calliman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in **COMMISSION**

<u>Ottawa</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>6N</u> R <u>15W</u>	<u>I-9</u>
	T _____ R _____	<u>(SE cor. Sec.</u>
	T _____ R _____	<u>22, Olive Twp)</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Douglas J. Koning, in a field survey on September 9, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L.C.R.C. L. 3 P. 320 1977	L.C.R.C. L. 5 P. 323 1988
I-9 "T" Iron in Mon. Box	I-9
Nail in Tel. pole SW 46.58'	Set CIM
Nail in Tel. pole NW 44.59'	T. Pole SW 46.5'
	T. Pole NW 44.6'
	Fence Post NE 41.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9 Found C.I. Mon. in Mon. Box  
Nail NW side Fence Post NE 41.05'

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9 C.I. Mon. in Box (In centerline crossing of N, S, E, & W Roads)  
Nail and O.C. Remon Tag in NE side Power Pole S31°W 123.55'  
Nail and O.C. Remon Tag in N side Power Pole S72°E 182.07'  
Nail and O.C. Remon Tag in W side of 26" Ash S 8°E 215.49'  
Nail and O.C. Remon Tag in NE side of Power Pole N44°W 92.09'

Signed by *Douglas J. Koning* Date 10-19-93  
Surveyor's Michigan License No. 35995

