

**SURVEY &  
REMONUMENTATION**

APR 05 1996

OTTAWA COUNTY REMONUMENTATION

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 NOV 15 PM 2:12

*Dorothy S. Ballman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Ottawa (County)	Located in:	Corner Code #
1. Public Land Survey	T 6N R15W	I-13
	T _____ R _____	(SW cor., Sec. 35
	T _____ R _____	Olive Twp.)
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Douglas J. Koning, in a field survey on October 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/of subsequent restoration:

I-13 Government Notes Set Post May 1832 Hemlock 20" N62°E 15 Links Leo 4" N67°W 45 Links	L.C.R.C. Liber 1, Page 585, August 1972 I-13 "T" Iron Centerline St. Sign S 28.22' 11" Ash SW 64.15' Pow. Pole NNW 103.24'
---	--

I-1 T5N, R15W Government Notes 1.10 Links (72.6') East of Post	L.C.R.C. Liber 3, Page 212, November 1977 I-13 Set Cast Iron Monument Pow. Pole SE 53.75' Pow. Pole NE 56.43' Centerline Hydrant NE 42.82'
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I-13 Found Cast Iron Monumnet in Box 0.7' deep Found PK NE side Guy Pole Found Tag & Nail SW side Pow. Pole Centerline Hydrant	NE 56.08' SE 53.50' NE 48.70'
---	-------------------------------------

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 10/23/95

*Kudoy D. McDowell*  
207

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

I-13 Cast iron Monumnet Set O.C. Remon Tag & Nail NE side Guy Pole Set O.C. Remon Tag & Nail SW side Pow. Pole Set O.C. Remon Tag & Nail N side Pow. Pole Centerline Top Hydrant Found Cast Iron Monumnet leaning In Centerline E,W & N Roads	N32°E 56.18' S40°E 53.51' S80°W 174.88' N50°E 48.70' EAST 72.50±
---	--

Signed by Douglas J. Koning  
Surveyor's Michigan License No. 35995

Date 10-20-95

