

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

RECORDED

94 DEC 15 AM 11:48

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

Dorothy Hollman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located in:	Corner Code #
1. Public Land Survey	T 6N R 15W	K-13
	T _____ R _____	(Sw cor., Sec. 36
	T _____ R _____	Olive Twp.)
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Douglas J. Koning, in a field survey on November 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/of subsequent restoration:

K-13 Government Notes	L.C.R.C. Liber 2, Page 225, June 1973
Set Post April 1832	K-13 Found Bent "T" Iron, Set Cast Iron Monument
By Calvin Britain, D.S.	36" Maple NE 45.81'
Hemlock 10" N83°W 45 Links	Power Pole NE 47.70'
Leo 10" N64°W 5 Links	Centerline Hydrant SE 62.38'
	Power Pole SW 29.91'
	Holland Twp. Cor. E 28.38'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

K-13 Cast Iron Monument (1.5' Deep)	
Found Nail in NWly side 36" Maple	N45°E 47.54'
Hydrant	S60°E 62.44'
Cast Iron Monument	E 28.19'


P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94
Kendy D. Newbold

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

K-13 Set Form Pin and O.C. Cap in Mon. Box over Cast Iron Monument
(1'± S of E-W Road, on Centerline of Road to N.)

Set O.C. Remon Nail & Tag in SEly side 36" Maple	N46°E 46.65'
Set O.C. Remon Nail & Tag in NWly side 16" Maple	S65°W 85.73'
Set O.C. Remon Nail & Tag in NWly side 14" Maple	S50°W 53.22'
Top Center Hydrant	S60°E 62.44'
Cast Iron Monument	E 28.19'



Signed by Douglas J. Koning
Surveyor's Michigan License No. 35995

Date November 21, 1994