

DEC 01 1998

SECTION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
98 JUL 21 PM 12:14

Long Schultz
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey

T6N R15W

L-13 (S1/4, 36)

T___ R___

Olive Twp.

T___ R___

T___ R___

2. Property Controlling in Section

S___

T___ R___

3. Miscellaneous Property in Sec.

S___

T___ R___

S___

T___ R___

S___

T___ R___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on March 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-13 GLO

LCRC 3-212

LCRC 3-322

Calvin Britain, 1832

Nov., 1971 Byl

Jan., 1979 Clapp

Set 1/2 mile post

"T" iron

TP NW 67.2'

Pine 3 N 43 W 55

Set CIM

TP ENE 194.59'

Pine 7 N 40 E 22

TP WNW 67.2'

TP ENE 194.58'

OVER

RA. 346 OTTAWA COUNTY
FEES APPROVED 6-1-98

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 Found 1/2" rerod in Mon. Box (0.05' from SW side of box); on C/L bit. road E & W; on field division North

As per Nederveld wit. on back

And is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Replaced rerod with 3/4" x 24" pin with Ottawa Co. Cap in Mon. Box

Note: Point is NOT in center of cap (rerod is a wedge)

Ottawa Co. Remon. Tag & Nail in SE side UP N 38° E 39.58'

Ottawa Co. Remon. Tag & Nail in S side UP N 80° W 208.80'

Ottawa Co. Remon. Tag & Nail in SW cor. garg. siding N 70° W 194.08'

SE cor. hse. fnd. N 55° W 167.15'

On C/L bit. road E-W; on field division North

Ottawa Co. Mon. in Mon. Box East 14.05' L-1 (N 1/4 1, 5-15)



Signed by

John C. Bueche

Surveyor's Michigan License No. 13027

Date

4-1-98

SURVEY &
REMONUMENTATION

DEC 01 1998

SECTION

L-13

PART A - continued

Nederveld, no date

Fnd. rerod in Mon. Box

Set mag. nail w/washer in PP N 37° E 39.42'

SE cor. hse. foundation N 35° W 167.12'

Set mag. nail w/washer in S side PP N 81° W 208.80'

Twp. Mon. to South East 14.07'

