

SURVEY & REMONUMENTATION

FEB 27 1998

SECTION

OTTAWA COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

RECORDED

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

97 OCT 30 AM 10:59

Ottawa <small>(County)</small>	Located in:	Corner Code #	
1. Public Land Survey	T 6N R15W	M-2	
	T _____ R _____	(E 1/4 cor., Sec. 1	
	T _____ R _____	Olive Twp.)	
	T _____ R _____		
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

Debra Gant
Register of Deeds
Ottawa County, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Douglas J. Koning, in a field survey on September 3, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-2 Government Notes Set Post May 1832 By Calvin Britain D.S. Black Ash 9" S22°W 17 Links Leo 10" N18°W 20 Links	L.C.R.C. Liber 1, Page 223, January 1972 M-2 Found Steel Bar NE cor. House SW 115.93' Nail in face of Tel. Pole SW 48.70' Nail in face of 6" Pine NE 50.15' Nail in face of 6" Pine SE 52.28'	L.C.R.C. Liber 3, Page 92, June 1976 M-2 5/8" Steel Rod Blendon Township Corner N 38.89' Utility Pole SW 48.76' NE House Corner SW 115.93' Se House Corner SW 173.63'
	L.C.R.C. Liber 3, Page 205, November 1977 M-2 Cast Iron Monument Power Pole NW 84.25' 30" Oak NE 60.95' 24" Maple SE 42.90' 12" Spruce SW 60.35'	L.C.R.C. Liber 4, Page 83, July 1980 M-2 Set Cast Iron Monument Inscribed "Section Corner" Power Pole SW 48.74' 10" Pine E 45.70' 10" Pine NE 60.53' Blendon Twp. Cor. N 38.89'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

M-2 Found Cast Iron Mon in Mon Box 1'± East of Centerline	
SE corner Brick House #9181	SW 173.58'
NE corner Brick House #9181	SW 115.89'
Found Nail & Tag in face of Tel. Pole	SW 48.71'
Found Nail & Tag in Sly side Tel. Pole	SW 49.13'
Found P.K. & Tag in Nly side Tel. Pole	SW 49.04'
Found Nail & Tag in NW side 14" Pine	NE 60.56'
Found Cast Iron Mon in Box	N 38.89'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/27/97
[Signature]

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner

M-2 Found Cast Iron Mon in Mon Box 1" East of Centerline	North	38.89'
Found Cast Iron Mon in Box	S61°W	49.01'
Set Ottawa County Remon Nail & Tag in NW side Tel. Pole	N62°W	89.04'
Set Ottawa County Remon Nail & Tag in NE side Power Pole	N55°E	60.44'
Set Ottawa County Remon Nail & Tag in NW side 14" Pine	S38°E	69.85'
Set Ottawa County Remon Nail & Tag in SW side 14" Pine	S37°W	173.58'
SE corner Brick House #9181	S57°W	115.89'
NE corner Brick House #9181	West	1'
Centerline North-South road		

4 9.00 CORNER
1.00 PHOTO

Signed by Douglas J. Koning Date 10-27-97

Surveyor's Michigan License No. 35995

