

**SURVEY &  
REMONUMENTATION**

APR 24 1995

OTTAWA COUNTY REMONUMENTATION

RECORDED

LAND CORNER RECORDATION CERTIFICATE

For corners in **COMMISSION** Filing Requirement of Act 74, Mich. P.A. 197094 DEC 15 AM 11:47

|                                       |                          |                 |
|---------------------------------------|--------------------------|-----------------|
| <u>Ottawa</u><br>(County)             | Located in:              | Corner Code #   |
| 1. Public Land Survey                 | T <u>6N</u> R <u>15W</u> | M-13            |
|                                       | T _____ R _____          | (SE cor., Sec.  |
|                                       | T _____ R _____          | 36, Olive Twp.) |
|                                       | T _____ R _____          |                 |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____  |                 |
|                                       | S _____ T _____ R _____  |                 |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____  |                 |
|                                       | S _____ T _____ R _____  |                 |
| 4. Lot No. _____, Recorded Plat _____ |                          |                 |
| 5. Private Claims _____               |                          |                 |

*Pollock Hartman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Douglas J. Koning, in a field survey on December 8, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |

A. Description of original monument and accessories and/of subsequent restoration:

M-13 Government Notes L.C.R.C. Liber 3, Page 322 January 1979  
 Set Post May 1832 M-13 Fnd. square iron over brass plug  
 By Calvin Britain D.S. Pwr. pole SE 85.88'  
 Beech 10" S73°E 25 Links Centerline hydrant NE 66.40'  
 Leo 7" N10°W 19 Links Pwr. pole SW 76.07'  
 Tel. pole NE 46.56'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.


M-13 Found Cast iron monument in mon. box  
 Found P.K. Nail in SE side Guy pole N50°E 46.79'  
 Found P.K. Nail in SW side Pwr. pole S35°E 86.63'  
 Found Nail in face of Pwr. pole S35°E 85.99'  
 Found Nail in SE side Pwr. pole S30°W 76.36'  
 Found Nail & Tag in NW side Pwr. pole S30°W 76.32'  
 Found P.K. Nail in Sly side Guy pole S45°W 39.26'  
 Hydrant N48°W 51.06'

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12/12/94  
*Maday P. McDowell*

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

m-13 Cast Iron Monument (in Centerline "X" of Roads)  
 O.C. Remon Nail & tag in SE side Pwr. pole S30°W 76.36'  
 O.C. Remon Nail & Tag in SE side Guy pole S45°W 39.21'  
 O.C. Remon Nail & TAG in NE side Pwr. pole S35°E 86.61'  
 O.C. Remon Nail & Tag in SE side Guy pole N50°E 46.69'  
 Top Centerline Hydrant N48°E 51.06'



Signed by Douglas J. Koning  
 Surveyor's Michigan License No. 35995

Date December 12, 1994