

FEB 24 2000

RECORDED

SECTION

OTTAWA COUNTY REMONUMENTATION

99 SEP 23 PM 3: 20

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

*Dany Scholtz*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

OTTAWA  
(County)

Located in:

Corner Code #

- 1. Public Land Survey      T6N R 15W      E-7 NW Corner
- T    R              Section 21, Olive
- T    R              Twp. \_\_\_\_\_
- T    R              \_\_\_\_\_
- 2. Property Controlling    S    T    R              \_\_\_\_\_
- in Section                S    T    R              \_\_\_\_\_
- 3. Miscellaneous            S    T    R              \_\_\_\_\_
- Property in Sec.         S    T    R              \_\_\_\_\_

*Seg 2*

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Randal J Vugteveen, in a field survey on September 16, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-7 Ottawa County Peer Approved Liber 1, Page 189 (Koning 1993)  
Cast Iron Monument (3' N of centerline "X" 1.1' deep)  
Nail & Remon Tag NE side 24" Maple N40°W 36.06'  
Nail & Remon Tag W side 24" Maple N30°E 51.77'  
Nail & Remon Tag S side 34" Maple N65°E 38.27'  
Nail & Remon Tag N side Power Pole S70°E 85.54'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7 on June 3, 1999 found Cast Iron Monument 1.1' Deep

<p>Found Nail &amp; Remon Tag W side 24" Maple N30°E 51.77'</p> <p>Found Nail &amp; Remon Tag in S side 34" Maple N65°E 38.29'</p> <p>Found Nail and Remon Tag in N side Power Pole S70°E 85.52'</p> <p>OCRC to rebuild road at this time</p>	<p>Accepted Cast Iron Monument as a careful and faithful perpetuation of the position of the original corner.</p> <p>Set iron witness points outside of construction zone.</p>
---	--

September 16, 1999 found Cast Iron Mon. 1.5 deep  
Checked distances to witness irons okay.  
Set 1.2' long X 3/4" solid bar & rebar cap on top of Cast Iron Monument

*9/20/99*  
*YDZ*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


E-7 1.2' long x 3/4" solid bar and Remon Cap on top of Cast Iron Monument

Found PK with Remon Tag in N side Power Pole S68°E 85.52'  
Set Nail and Remon Tag in W side 7" poplar S26°W 71.27'  
Set Nail and Remon Tag in N side 12" poplar S60°W 67.03'  
Set Nail and Remon Tag in W side 5" Mulberry N24°E 71.09'  
Found "T" iron S45°W 47.39'

Centerline gravel road (soon to be paved) 1' South  
Centerline gravel road to North 3' West  
Centerline gravel road to South 0' West

Signed by *Randal J. Vugteveen*  
Surveyor's Michigan License No. 28429

Date SEPT. 20, 1999



\$9.00 CORNER  
Receipt #58324

Receipt #  
\$1.00