

SURVEY & REMONUMENTATION

APR 05 1996

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

For corners in

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 NOV 15 PM 2:08

| Ottawa (County) | Located in: | Corner Code # |
|---------------------------------------|-------------------------|----------------------|
| 1. Public Land Survey | T 6N R 15W | 1-6 |
| | T _____ R _____ | (E 1/4 cor., Sec. 35 |
| | T _____ R _____ | Olive Twp.) |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 4. Lot No. _____, Recorded Plat _____ | | |
| 5. Private Claims _____ | | |

Ruthie Bellman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Sequence # 2

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | ▲ | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Douglas J. Koning, in a field survey on October 14, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3,4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/of subsequent restoration:

| | | |
|------------------------|--|--|
| I-6 Government Notes | L.C.R.C. Liber 1, Page 425, June 1972 | L.C.R.C. Liber 2, Page 711 November 1974 |
| Set Post May 1832 | I-6 Found Stake & Brick (Midway on Line) | I-6 Fence cor. post N20°W 70.11' |
| Pine 6" S65°W 63 Links | Set Cast Iron Monument | Square wood post N70°W 59.22' |
| Pine 8" N54°E 20 Links | 18" Maple W 11.58' | Street sign post N15°W 18.53' |
| | 18" Aspen SSW 183.80' | N end headwall S30°W 20.41' |
| | Street Sign NNW 18.75' | N end headwall S45°E 33.20' |
| | Centerline 112th Avenue E 10' | |

OTTAWA COUNTY REMONUMENTATION

L.C.R.C. Liber 1, Page 124 November 1993
I-6 C.I. Mon. Centerline of 112th Avenue 10' East
Set Nail & O.C. Remon Tag SE side Lgt. Pole N35°E 186.18'
Set Nail & O.C. Remon Tag NW side Pow. Pole N10°E 206.86'
Set Nail & O.C. Remon Tag S side Pow. Pole S87°W 25.32'
Set Nail & O.C. Remon Tag E side 10" Maple S5°W 70.87'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

Keddy P. Nedewell
MDN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

I-6 Found C.I.M. 2' Deep (Road under reconstruction)
Found O.C. Tag & Nail W side Pow. Pole N10°E 206.86'
Found O.C. Tag & Nail SE side Lgt. Pole N35°E 186.18'

This marker is accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

| | | |
|--|-------|---------|
| I-6 Set O.C. Remon Cap and Iron above Cast Iron Monument | | |
| O.C. Remon Tag & Nail W side Pow. Pole | N10°E | 206.86' |
| O.C. Remon Tag & Nail NW side Pow. Pole | N35°E | 186.18' |
| Set O.C. Remon Tag & Nail S side Pow. Pole | N86°E | 294.17' |
| Set O.C. Remon Tag & Nail NE side Pow. Pole | N30°W | 40.00' |
| Set O.C. Remon Tag & Nail E side End of Southerly CMP | S40°E | 53.89' |

Signed by Douglas J. Koning Date 10-20-95
Surveyor's Michigan License No. 35995

