

SURVEY &
REMONUMENTATION

APR 05 1996

OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey T6N R16W F-9 N 1/4 Cor.
T R Sec. 28
T R Port Sheldon Twp.
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED

95 NOV 15 PM 2:07

Dorothy Callahan
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Steven Lampen, in a field survey on September 7, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-9 Gov't Land Office Survey Notes
1832-Surveyor, Calvin Britain
Set 1/2 mile post
8" Beech N 34° W 22 links
12" Hemlock S 37° E 7 links

F-9 Recorded in Liber 3,
Page 87, June 14, 1976
Fd conc. mon. from Co. ties
18" Oak N90°W 61.50'
15" Twin Oak S15°W 36.58'
"T" Iron N02°W 50.00'
Power pole S47°E 59.49'

F-9 Recorded in Liber 5,
Page 181, Dec. 27, 1984
Fd conc. mon., set CIM
20" Oak NW 63.00'
Power pole E 59.44'
6" Oak N 26.83'
9" Oak W 27.15'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9

Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner.

Found nail in N side 12" Oak AZ 295° 27.14'
Found nail & tag in E side 8" Oak AZ 18° 26.80'
Found "T" Iron AZ 00° 50.02'
Found P.K. in NE side 12" twin Oak AZ 220° 36.54'
Found P.K. in E side 20" Oak AZ 279° 61.31'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

MDW Rodney P. Redwood

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9

Found cast iron monument
Large "T" Iron AZ 00° 50.02'
O.C. remon. tag & nail in E side 8" Oak AZ 18° 26.71'
O.C. remon. tag & nail in S side power pole AZ 100° 59.55'
O.C. remon. tag & nail in W side 12" Pine AZ 167° 42.96'
O.C. remon. tag & nail in N side 12" twin Oak AZ 220° 37.14'
O.C. remon. tag & nail in SW side 12" Oak AZ 295 27.25'
SE corner of house 4.5' above deck AZ 61° 205.61'
P.K. W face of power pole AZ 352° 214.90'



Signed by Steven Lampen

Date October 23, 1995

Surveyor's Michigan License No. 37279