

SURVEY & REMONUMENTATION

APR 24 1995

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 9:43

For corners in **COMMISSION**

Deborah A. Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County) Located In: Corner Code #

1. Public Land Survey T ~~6N~~ R 16W G-4 W1/4 Cor-
T R Sec 10
T R Port Sheldon Twp.
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	10	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, John P. Clapp, in a field survey on December 3, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-4 Govt Land Office Survey Notes
1832-Surveyor, Calvin Britain
Set 1/2 Mile Post
12" Hemlock S11°E 8 links
10" Hemlock N6°W 20 links

G-4 Recorded in Liber 5,
Page 277, Aug 17, 1987
Fd 1 1/2" Iron Pipe in Mon Box
Set Cast Iron Monument
8" Spruce NNW 102.79'
4" Cherry NE 71.67'
4" Pine S 29.29'

G-4 Recorded in Liber 5
Page 319, Aug 9, 1988
Set Cast Iron Monument
8" Spruce NNW 102.79'
4" Cherry NE 71.67'
4" Pine S 29.29'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4

Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

Found Nail in NW Side 8" Cherry AZ 36° 71.57'
Found Nail in E Side 10" Pine AZ 177° 29.38'
Found Nail in WSW Side 14" Pine AZ 348° 102.73'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4


Found Cast Iron Monument in Monument Box

O.C Remon Tag & Nail in W Side 10" Pine AZ. 177° 29.47'
O.C. Remon Tag & Nail SE Side 8" Cherry AZ. 36° 71.61'
O.C. Remon Tag & Nail WSW Side 14" Pine AZ. 348° 102.74'
O.C. Remon Tag & Nail in SW Side 6" Cherry AZ. 208° 171.07'

Signed by John P. Clapp

Surveyor's Michigan License No. 14091

Date Dec. 6, 1994



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983