

**SURVEY &
REMONUMENTATION**

OTTAWA COUNTY REMONUMENTATION

APR 05 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

Ottawa _____ Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T6N R16W G-6
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

RECORDED

95 NOV 15 PM 2:08

Dorothy Kellerman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Steven Lampen _____, in a field survey on October 23 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-6 No LCRC recorded
 GLO Survey Notes
 1832, Surveyor - Samuel Marrs
 Set 1/2 mile post
 7" Cherry S 83° E 25 links
 4" Cherry N 87° W 30 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-6
 Corner is inaccessible as it falls under a large active coal pile. Corner position was determined from survey information by Consumers Power Co.

PA. 345 OTTAWA COUNTY
 PEER APPROVED 10/23/95

Gregory D. Hedewell

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-6
 Corner falls under large active coal pile at C. P. Co., J.H. Campbell Plant.

G-5 359° 04' 02" 2643.67' H-5 44° 21' 55" 3715.07' I-6 90° 00' 15" 5315.47'
 G-7 179° 07' 50" 2633.75' H-7 134° 17' 36" 3779.86'

AZ = MI State plane grid direction

Signed by *Steven Lampen*

Date October 23, 1995

Surveyor's Michigan License No. 37279



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993