

**SURVEY & REMONUMENTATION**

OCT 24 1994

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 OCT -7 PM 12:32

*Robert A. Ballman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>16W</u>	<u>G-13 (SW Cor. Sec 34)</u>
	T _____ R _____	<u>Port Sheldon-Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Gerald T. Ford, in a field survey on April 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

<b>G-13</b>	<b>G-13</b>
Government Land Office Survey Notes	Recorded in Liber 1, Page 347, April 10, 1972
1832 - Surveyor, Calum Britian	Steel Bar
Post	USGS Benchmark
10" Pine N80°W 10 links	WNW 94.55'
10" Pine N34°E 14 links	SW 54.82'
	Nail in face of 6" Maple SE 58.19'
	Nail in face Park Twp Corner W 90.43'
	Nail in NW Cor W Gate Pillar SE 72.31'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**G-13**  
Found 3/4" steel bar and accepted it as a careful and faithful perpetuation of the position of the original corner  
Found nail & tag NW side 12" maple AZ 218° 19' 55.13'  
Cast iron mon. in mon box. (G-1 T5N R16W) AZ 270° 16' 90.44'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 6/20/94  
 *Gordon D. Hildebrand*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<b>G-13</b>	
Set O.C. Remon cap & iron in mon. box	
AZ - Michigan State Grid Direction	
O.C. Remon tag & nail in N face p. pole	AZ. 74°44' 128.46'
NE Cor conc. pillar 1' above ground	AZ. 114°48' 73.79'
O.C. Remon tag & nail in NE face 30" maple	AZ. 152°52' 37.41'
O.C. Remon tag & nail in N face p. pole	AZ. 284°32' 129.01'
Cast Iron Mon. in Mon Box (G-1 T5N, R16W)	AZ. 270°16' 90.44'



Signed by Gerald T. Ford Date July 13, 1994  
Surveyor's Michigan License No. 33976