

**SURVEY &
REMONUMENTATION**

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 10:02

Deborah Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T <u>6N</u> R <u>16W</u>	<u>H-3 N1/4 Cor</u> <u>Sec 10</u> <u>Port Sheldon Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, John P. Clapp, in a field survey on December 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-3 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain 12" Hemlock is post	H-3 Recorded in Liber 1, Page 679, Oct 13, 1972 Found 1" Iron Pipe 16" Ash NW 31.52' Fence line W 25.0' 6" Ash NNE 23.94' 12" Ash ENE 64.40' 6" Pine SSE 37.01'	H-3 Recorded in Liber 3 Page 303, Oct. 30, 1978 Found Cast Iron Monument 16" Poplar N 29.16' 28" Cherry WNW 53.08' Quad Cherry ESE 62.83'
See reverse side for additional recordings. Liber 5, Page 287		

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-3
Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner.
Found Nail & Tag in E Side 22" Ash AZ 08° 29.11'
Found Nail & Tag in SE Side 12" Ash AZ 47° 41.15'
Found Nail in SW Side 12" White Pine AZ 154° 58.68'
Found Nail & Tag in NW Side 10" White Pine AZ 216° 55.28'


P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13 Found Cast Iron Monument		
O.C. Remon Tag & Nail in SE Side 12" Ash	AZ. 47°	41.10'
O.C. Remon Tag & Nail in SW Side 12" White Pine	AZ. 154°	58.68'
O.C. Remon Tag & Nail in NW Side 10" White Pine	AZ. 216°	55.25'
O.C. Remon Tag & Nail in SW Side 8" Tri Cherry	AZ. 324°	45.30'

Signed by John P. Clapp Date Dec. 6, 1994

Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, MAY 14, 1975
REVISED JAN., 1983

H-3
Recorded in Liber 5,
Page 287, March 18, 1988
Cast Iron Monument

16" Poplar	N	29.16'
8" Pine	SW	55.27'
Twin 10" Cherry	NW	83.27'
10" Pine	SE	58.72'
12" Ash	NE	41.18'

RECORDED
INDEXED
MAR 21 1988