

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

For corners in

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 9:43

D. J. ...
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 16W	H-5 N1/4 Cor
	T R	Sec 15
	T R	Port Sheldon Twp.
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John P. Clapp, in a field survey on December 3, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

H-5 Govt Land Office Survey Notes
1832-Surveyor, Calvin Britain
Set Post
14" Beech N55°W 9 links
12" Beech S38°E 20 links

H-5 Unrecorded ties from 1971
Set Cast Iron Monument in Place of Iron Pipe
20" Cherry S 39.61'
6" Red Pine SW 45.43'
3" Cherry NE 38.15'
5" Cherry NNE 83.86'
4" Cherry SE 52.99'

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


H-5
Found cast iron monument (top missing) and accepted it as a careful and faithful perpetuation of the position of the original corner
CL 14" Cherry (could not find nail) AZ 07° 84.00 ± to CL

Robert P. Redwood P.A. 345 OTTAWA COUNTY
PEER APPROVED 12/12/94

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5
Found Cast Iron Monument (top missing)
O.C Remon Tag & Nail in SE Side 6" Pine AZ. 54° 68.08'
O.C. Remon Tag & Nail in N Side 6" Cherry AZ. 103° 139.46'
O.C. Remon Tag & Nail in SE Side 10" Poplar AZ. 226° 38.65'
O.C. Remon Tag & Nail in SW Side 10" Cherry AZ. 336° 82.77'

Signed by John P. Clapp *John P. Clapp* Date Dec 6, 1994
Surveyor's Michigan License No. 14091



FORM APPROVED BY MICHIGAN STATE BOARD OF SURVEYORS JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1993