

SURVEY &
REMONUMENTATION

APR 05 1996 OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
COMMISSION Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa _____ Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T6N R16W H-9
T _____ R _____ S 1/4 cor. Sec.
T _____ R _____ 22, Port
T _____ R _____ Sheldon Twp.

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

RECORDED
95 NOV 15 PM 2:06
Elyse S. Holloman
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven Lampen _____, in a field survey on October 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO	LCRC L1-P 315	LCRC L1-P 717
May 1832	Nail in side 10" Cherry	Section corner marker
Surveyor- Calvin Britain	Nail in side 12" Cherry	Nail in side 6" Pine
Set post	Nail in side 8" Pine	SSW 54.34'
10" Beech N 85° E 20'	Nail in side 8" Pine	Nail in side 10" W. Cherry
18" Beech S 65° W 7'		WNW 31.13'
		Nail in side 10" twin W. Cherry
		NE 40.63'
		Centerline B. T. road
		S 17.6'

Continued on reverse side

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found CIM and is accepted as a careful and faithful perpetuation of the position of the original corner.

Nail in side 10" Cherry	NE 40.62'	Nail in side 6" Pine	SSW 54.34'
Nail in side 12" Cherry	WNW 31.16'	Nail in side 10" W. Cherry	WNW 31.13'
Nail in side 8" Pine	SW 54.31'	Nail in side 10" twin W. Cherry	NE 40.63'

Continued on reverse side

P.A. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

Andrew P. McDowell S.D.M.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-9	AZ = MI State plane grid direction
CIM	180° 17.2'
Centerline asphalt pavement	291° 45' 31.21'
Remon. tag N side 16" Cherry	23° 18' 79.05'
SW corner house foundation	201° 07' 54.13'
Remon. tag in W side 16" Pine	161° 32' 115.75'
NW corner house foundation	



Signed by Steven Lampen

Date October 23, 1995

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

A. Cast iron monument
 12" Cherry WNW 30.53'
 SW house corner NE 79.10'
 Centerline road S 18.20'
 Concrete monument N 43.00'

B. 12" Cherry WNW 30.53'
 SW house corner NE 79.10'
 concrete monument N 43.00'

* 11.00 CORNER