

SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

94 DEC -8 PM 12: 31

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|--------------------------|-------------------------------|
| 1. Public Land Survey | T <u>6N</u> R <u>16W</u> | <u>H-11 (N1/4 Cor Sec 34)</u> |
| | T _____ R _____ | <u>Port-Sheldon Twp:</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Register of Deeds
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

John P. Clapp

November 16,

94

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-11 Gov't Land Office Survey Notes
May 1832 - Surveyor, Calvin Britain
Post
12" Hemlock N74°W 21 links
5" Hemlock S73°E 10 links

H-11 Recorded in Liber 1,
Page 155, Nov 23, 1971
Set CIM in place of angle iron
PP NW 77.23'
36" Beech SW 47.16'
8" Oak SW 52.02'
18" Twin Oak SSW 63.78'
PP SE 27.40'
CL St Sign SE 84.90'

H-11 Recorded in Liber 1
Page 607, Aug. 29, 1972
Found Cast Iron Monument
Guy Pole NW 77.75'
Power Pole SE 27.73'
28" Beech SW 47.70'
CL Butternut E 40' ±

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11

Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner

Found Nail & Cap in Face Power Pole	AZ. 298°	77.21'
Found Nail & Cap in SW Side Power Pole	AZ. 298°	77.71'
CL Butternut	AZ. 90°	41.4' ±
Found Nail & Tag NE Side 12" Pine	AZ. 306°	121.18'
Found Scar N Side 18" Oak	AZ. 251°	80.68'
Found Scar NW Side 17" Oak	AZ. 215°	64.61'

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

Handwritten signature

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11

Found Ottawa County Cast Iron Monument		
O.C. Remon tag & nail in NE Side 12" Pine	AZ.	306° 121.15'
O.C. Remon tag & nail in NW Side 17" Oak	AZ.	215° 64.60'
O.C. Remon tag & nail in NE Side 26" Oak	AZ.	143° 134.41'
O.C. Remon tag & nail in NW Side Light Pole	AZ.	47° 68.26'



Signed by John P. Clapp

Handwritten signature of John P. Clapp

Date Nov. 17, 1994

Surveyor's Michigan License No. 14091