

# SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

*Deborah L. Williams*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

For corners in

Ottawa (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 16W	I-2 W1/4 Cor
	T R	Sec 2
	T R	Port Sheldon Twp.
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, John P. Clapp, in a field survey on December 3, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-2 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set 1/2 mile post 6" Hemlock N69°E 6 links 3" Hemlock S19°W 5 links  See reverse side for additional recordings L.5, P. 66 & L.5, Pg 289	I-2 Recorded in Liber 1, Page 679, Oct 13, 1972 Found Iron Pipe 4" Sassafras SW 39.96' 20" Maple SE 58.00' CL St. Sign SE 37.67' 16" Maple ESE 83.81' 12" Maple WSW 68.85'	I-2 Recorded in Liber 4 Page 162, April 1, 1981 Fd. Iron, Set Cast Iron Monument Power Pole NW 69.75' T. Pedestal SW 39.71' Power Pole NE 56.40' 31" Maple SE 60.00'
--	---	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*Robert D. Nedeweld*

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12/12/94

I-2  
 Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner

CL St. Sign	AZ 138°	41.22'
Found Nail & Tag in SW Side Power Pole	AZ 312°	69.71'
CL Telephone Pedestal	AZ. 225°	47.86'
Found Nail & Tag in NW Side Power Pole	AZ. 36°	56.39'
Found Nail & Tag in ENE Side 32" Maple	AZ. 154°	59.96'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


I-2  
 Found Cast Iron Monument in Monument Box

O.C. Remon Tag & Nail in SE Side Power Pole	AZ. 36°	56.47'
NW Corner Garage Foundation	AZ. 142°	238.49'
O.C. Remon Tag & Nail in N Side Twin Oak	AZ. 250°	96.67'
SE Corner House Foundation	AZ. 332°	158.56'

Signed by John P. Clapp *John P. Clapp*  
 Surveyor's Michigan License No. 14091

Date Dec. 6, 1994

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS. JAN. 25 1971  
 REVISED 1975  
 1983



I-2  
 Recorded in Liber 5,  
 Page 66, Sept 22, 1983  
 Fd. Cast Iron Monument

Power Pole	NE	56.39'
30" Maple	SE	59.95'
T. Pedestal	SW	39.57'
Power Pole	NW	69.71'

I-2  
 Recorded in Liber 5  
 Page 289, Mar. 18, 1988 *CAST IRON MON.*

Power Pole	NW	69.75'
T. Pedestal	SW	47.90'
Power Pole	NE	56.40'
31" Maple	SE	60.00'

CODE #  
 2000  
 2000  
 2000  
 2000