

SURVEY & REMONUMENTATION

APR 24 1995

COMMISSION

Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC 14 AM 9:43

Richard R. Beldman
 REGISTER OF DEEDS
 OTTAWA COUNTY, MI

For corners in

Ottawa (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 6N R 16W I-7 NW Cor
 T _____ R _____ Sec 23
 T _____ R _____ Port Sheldon Twp.
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

John P. Clapp November 18, 1994

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-7 Gov't Land Office Survey Notes May 1832 - Surveyor, Calvin Britain Post	I-7 Recorded in Liber 2, Page 693 October 22, 1974 Found Steel Bar
15" Beech S75°W 22 links	12" Maple S86°E 22.99'
6" Hemlock N85°E 14 links	12" Maple N10°E 32.12'
	20" Maple N79°W 47.02'
	12" Twin Cherry S30°E 38.53'
	E & W Fence S 55' ±

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7
 Found 3/4" steel bar and accepted it as a careful and faithful perpetuation of the position of the original corner

18" Maple	AZ. 104°	22.91' (R)	22.86' (M) to scar
20" Maple	AZ. 12°	32.12' (R)	31.88' (M) to scar
Found Nail in East Side 24" Maple	AZ. 291°	47.00'	
Found Nail & Tag in NW Side 18" Twin Cherry	AZ. 152°	38.55'	

P.A. 345 OTTAWA COUNTY

PEER APPROVED 12/12/94


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7
 Set O.C. Remon Cap & Iron

O.C. Remon tag & nail in SW Side 18" Maple	AZ. 104°	23.02'
O.C. Remon tag & nail in NW Side 12" Cherry	AZ. 217°	35.37'
O.C. Remon tag & nail in NE Side 18" Tw Maple	AZ. 300°	49.02'
O.C. Remon tag & nail in SW Side 20" Maple	AZ. 12°	32.08'

Signed by John P. Clapp *John P. Clapp*
 Surveyor's Michigan License No. 14091

Date Dec 5, 1994



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 14, 1975
 REGISTERED LAND SURVEYOR, JAN., 1983