

SURVEY & REMONUMENTATION

DEC 01 1993

COMMISSION

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

93 NOV 11 AM 11:56

Elizabeth Callahan
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 16W	19 (NW Sec. 26)
	T _____ R _____	Port Sheldon Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, David R. Greer, in a field survey on September 13, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 5 Page 98, Dec. 20, 1983

I-9

Set cast iron monument

LP	NE	38.00
Tele Ped	SW	52.25
8" Elm	NW	98.24
10" B Cherry	SE	84.75

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-9

Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

LP	NE	38.00
Tele Pad	SW	52.25
8" Elm	NW	98.24
10" B Cherry	SE	84.75


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-9

C.I.M. in Monument Box

AZ - Michigan State Plane Grid Direction

OC Remon tag & nail in NW side 12" Cherry	AZ.	240°21	142.67'
OC Remon tag & nail in NE side 10" Cherry	AZ.	137°51	86.24'
OC Remon tag & nail in SE side 10" Maple	AZ.	59°02	97.96'
OC Remon tag & nail in SW side Twin 10" Ash	AZ.	319°04	98.06'



Signed by

David R. Greer

Date

SEPT. 13, 1993

Surveyor's Michigan License No.

16042

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983