

**SURVEY &  
REMONUMENTATION**

DEC 01 1993

**COMMISSION**

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

93 NOV 11 AM 11:55

*Deborah Holloman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

_____ Ottawa _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T <del>6N</del> R <del>16W</del>	<del>I-10 (E-1/4 Sec-27)</del>
	T _____ R _____	Port Sheldon Twp.
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David R. Greer, in a field survey on September 18, 19 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 4 Page 283, Jan. 5, 1982

I-10

Set cast iron monument

16" Maple	E	58.91
8" Birch	NE	46.92
16" Willow	NW	72.34
Tw. 12" Cherry	SW	45.60

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10

Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

16" Willow	NW	72.34
Tw. 12" Cherry	SW	45.60

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10

Raised C.I.M. in monument box with O.C. Remonument Iron & Cap

AZ - Michigan State Grid Direction

O.C. Remon tag & nail in NW Side Twin 10" Cherry	AZ.	236°09'	45.52
O.C. Remon tag & nail in S Side P. Power	AZ.	80°24'	29.44'
O.C. Remon tag & nail in S Side 24" Maple	AZ.	88°48'	71.32'
O.C. Remon tag & nail in SW Side 6" Maple	AZ.	115°43'	55.28'



Signed by David R. Greer

Date SEPT 18, 1993

Surveyor's Michigan License No. 16042