RECORDED

94 OCT -7 PM 12: 32

REGISTER OF DEEDS
OTTAWA COUNTY, MI

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Ottawa (County)

	Located In:	Corner Code ##
1. Public Land Survey	T 6N R 16W	I-13 (SE Cor. Sec 34)
	T ___ R ___	Port Sheldon Twp.
	T ___ R ___	
	T ___ R ___	
2. Property Controlling	S ___ T ___ R ___	
in Section	S ___ T ___ R ___	
3. Miscellaneous	S ___ T ___ R ___	
Property in Sec.	S ___ T ___ R ___	

Register of Deeds Stamp & File Number

4. Lot No. _____ , Recorded Plat _____
5. Private Claims _____



I, Gerald T. Ford, in a field survey on April 1, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13
Government Land Office Survey Notes
1832 - Surveyor, Calum Britian
Post

8" Beech	N53°E	22 links
30" Pine	N56°W	42 links

I-13
Recorded in Liber 1 Page 347 April 10, 1972
Set cast iron monument

Park Twp Corner	W	26.54'
Power Pole	S	26.19'
14" Pine	N	55.26'
T Pole	WSW	83.09'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13
Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the orginal corner

Found C.I. M. in Mon Box (I-1, T5N, R16W)	AZ 270°17'	26.49'
Found Nail & Tag N Face Guy Pole	AZ 252° 40'	83.06'
Found Nail & Tag E Face P. Pole	AZ 169° 30'	26.25'

P.A. 345 OTTAWA COUNTY
PEER APPROVED 6/20/94
Gordon D. Wiederwelt

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13
Cast iron monument in monument box

"X" cut top of W. spigot hydrant	AZ. 179°11'	106.95'
NW cor cinder blk fd. Park Twp water building	AZ. 149°55'	86.23'
NE cor cinder blk fd Park Twp. water building	AZ. 144°12'	92.19'
Set O.C. Remon tag & nail in N face Guy Pole	AZ. 252°40'	82.96'
O.C. CIM in mon box (I-1 T5N R16W)	AZ. 270°17'	26.49'

STATE OF MICHIGAN
GERALD T. FORD
SURVEYOR No. 33976
LICENSED LAND SURVEYOR

Signed by Gerald T Ford Date July 13, 1994

Surveyor's Michigan License No. 33976

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 19
REVISED MAY 14, 19
REVISED JAN., 19

W:\Deed\SurvRemon.doc