

**SURVEY & REMONUMENTATION**

DEC 01 1993

COMMISSION

**OTTAWA COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 NOV 11 AM 11:56

*Richard Carlstrom*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
Ottawa

(County)

Located In:

Corner Code #

1. Public Land Survey	T	6N	16W	J-3 (N 1/4 Sec 11)
	T			Port Sheldon Twp.
	T			
	T			
2. Property Controlling in Section	S			
	S			
3. Miscellaneous Property in Sec.	S			
	S			

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3					2			1
3									•			
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, David R. Greer, in a field survey on September 15, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Recorded in Liber 1 Page 745 Dec, 8, 1972

J-3

Found 2" Iron Pipe

Set Cast Iron Monument

24" Twin Beech	NW	80.06'
24" Quad. Maple	NE	60.45'
12" Pine	S	31.63'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-3

Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner

24" Twin Beech	NW	80.06'
24" Quad Maple	NE	60.45'
12" Pine	S	31.63'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-3

C.I.M. in monument box

AZ - Michigan State Grid Direction

O.C. Remon tag & nail in SE Side 14" Pine	AZ.	226°44'	60.98'
O.C. Remon tag & nail in NE Side 12" Pine	AZ.	324°24'	88.32'
O.C. Remon tag & nail in SE Side 28"	AZ.	61°47'	107.32'
O.C. Remon tag & nail in SW Side 8" Pine	AZ.	144°54'	58.96'



signed by

*David R. Greer*

Date

Sept. 15, 1993

Surveyor's Michigan License No.

16042