

SURVEY & REMONUMENTATION

OCT 24 1994

COMMISSION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 OCT -7 PM 12:32

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 16W	J-13 (South 1/4 Cor- 35)
	T R	Port-Sheldon Twp.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Dorothy C. Redman
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Gerald T. Ford, in a field survey on April 1, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:			
J-13	J-13 Recorded in Liber 2 Page 23 Feb. 16, 1973		
Government Land Office Survey Notes	Angle Iron		
1832 Surveyor, Calum Britian	6" Iron	N	55.30'
Post	T Pole	NE	68.02'
12" Beech N16°E 33 links	8" Pipe	SE	74.81'
12" Beech N43°E 37 links	24" Maple	S	79.90'
	T. Pole	S	45.65'
	12" Spruce	SW	56.32'
	Park Twp Cor	W	10.10'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

P.A. 345 OTTAWA COUNTY
PEER APPROVED 6/20/94

J-13	Found cast iron monument in monument box and accepted it as a careful and faithful perpetuation of the position of the original corner	
	Found Nail & Tag W Face of Power Pole	AZ 195° 45.67'
	Found Nail S Face Power Pole	AZ 33° 67.97'
	Face of Spruce	AZ 225° 56.1 ±
	Found angle iron in Mon box (J-1, T5N, R16W)	AZ 270°26' 10.15'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13	Found O.C.I.M. in monument box	
AZ - Michigan State Grid Direction		
O.C. Remon tag & nail in S face twin 6" Maple	AZ. 295°30'	76.46'
O.C. Remon tag & nail in SE face T. Pole	AZ. 33°13'	68.24'
O.C. Remon tag & nail in N face T. Pole	AZ. 196°11'	45.92'
NW Corner Conc Hse Foundation (1' above Grd)	AZ. 161°29'	107.83'
Angle iron in mon. box (J-1, T5N, R16W)	AZ. 270°26'	10.15'



Signed by Gerald T. Ford Date July 13, 1994
Surveyor's Michigan License No. 33976