

**Ottawa County Remonumentation
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
96 DEC 18 PM 4:54

Dorothy Williams
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in Ottawa (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 6N R 16W K-1
 T _____ R _____ Port Sheldon
 T _____ R _____ Twp. _____
 T _____ R _____ NW CORNER
 SECTION 1

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec. S _____ T _____ R _____
 S _____ T _____ R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Steven Lampen, in a field survey on Nov. 7 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1 GLO-Britain 1832 North boundary .31 West of post set corner Hemlock 10 S12E 25 Hemlock 6 S29W 47	LCRC L3 P99-1976 Found 1" pipe E. Grand Haven cor 20.99 NE P.P. 81.34 SE guy pole 80.47	LCRC L4 203-1980 Found 1" pipe - set cast iron monument Power pole NE 81.97 Guy pole SE 86.52 Wolverine pipeline sign East 121.77 Grand Haven cor East 21.00
---	---	---

LCRC 16 P69 - 1990
 Found cast iron monument
 East 21.00 to Grand Haven Twp cor K-13
 NE 63.03 to nail in W side 4" cedar
 NW 158.53 to nail in E side power pole
 SW 160.27 to nail in N side 16" oak
 SSE 112.41 to nail in NW side 10" oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1 found cast iron monument in monument box
 E Grand Haven cor. 20.99
 NE P.P. 81.34
 SE guy pole 80.47
 NE 63.03 to nail in W side 4' cedar
 NW 15.53 to nail in E side power pole
 SW 160.27 to nail in N side 16" oak

Established corner at intersection of West line Section 1 with the South line of Section 35, T7N, R16W and accepted it as a careful and faithful perpetuation of the position of the original corner.

P.A. 345 OTTAWA COUNTY
PEER APPROVED 12-9-96
M.P.N.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1
 Established corner at the intersection of the West line Section 1 with the South line of Section 35 T7N, R16W. Az. = Michigan State Plane Grid Direction.

Centerline east and west asphalt road pavement	N	0
Cast iron monument in monument box	179°03'	0.07
K-13 T7N, R16W - cast iron monument in monument box	90°51'	20.98
NGS BM R 317	56°59'	117.42
Centerline pipeline sign	62°04'	101.1
Nail W side twin 12" oak	163°29'	112.41
Nail NW side 18" oak	238°16'	160.31
Nail SW side power pole	309°49'	158.55



Signed by Steven Lampen Date November 11, 1996

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983
 ADAPTED FOR WORD PROCESSING MARCH, 1993