

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**RECORDED**

96 DEC 18 PM 4: 57

For corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 16W	L-1
	T R	North 1/4
	T R	corner
	T R	Section 1
2. Property Controlling in Section	S T R	Port
	S T R	Sheldon Twp.
3. Miscellaneous Property in Sec.	S T R	
	S T R	

*Elizabeth Hartman*  
**REGISTER OF DEEDS  
OTTAWA COUNTY, MI**

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steven Lampen, in a field survey on December 6 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

L-1	LCRC L5 P307-1988	LCRC L6 P30-1989
GLO corner not set by GLO	Found angle iron 8" Jack Pine NNE 30.29 10" Red Pine SE 43.48 8" Jack Pine NE 68.40 10" Pine NW 79.00	Found angle iron, set cast iron monument 12" Red Pine SE 52.50 10" Jack Pine NE 47.22 12" Red Pine S 64.96 S 1/4 cor Sec 36-7-16 E 16.15

LCRC L6 P69-1990  
Found cast iron monument  
East 16.15 to cast mon  
East 9.93 to 1/2" iron rod  
NNW 52.22 to PK nail E side 6" oak  
SE 43.25 to nail and cap N side 12" pine  
NE 30.28 to nail and cap W side 6" oak

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-1  
Found cast iron monument in monument box  
12" Red Pine SE 52.50 East 16.15 to cast monument  
12" Red Pine S 64.96 NNW 52.22 to PK nail E side 6" oak

This corner not monumented by the original GLO survey. This monument is accepted as the best available evidence of the position of the corner. Established corner at the intersection of the North and South 1/4 line of Section 1 with the South line of Section 36 T7N, R16W and set an Ottawa County Remonumentation iron and cap in a (set) monument box.

**P.A. 345 OTTAWA COUNTY**  
**PEER APPROVED** 12-9-96  
*M. D. N.*

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-1 Ottawa County Remonumentation iron and cap in a monument box		
Azimuth - Michigan State Plane Grid Direction		
Cast iron monument in monument box	359°00'	0.93'
L-13, T7N, R16W = cast iron monument in mon box	91°09'	16.10'
Remon tag in North side 14" oak	72°05'	147.52'
Remon tag in North side 12" pine	116°51'	78.53'
Remon tag in West side 12" pine	162°40'	61.07'
Remon tag in West side 8" oak	335°06'	52.83'
Centerline East and West asphalt road pavement	180°	0.1'
Mid-point K-1 and M-1	91°09'	5.66'



Signed by Steven Lampen Date DECEMBER 13, 1996  
Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1976  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1983

Z

