

DEC 01 1998

SECTION

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

98 SEP 29 PM 1:56

Don Schiller
REGISTER OF DEEDS
OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

For corners in

OTTAWA

(County)

Located In:

Corner Code #

1. Public Land Survey

T 6N R 16W

L-3 (N 1/4 Cor Sec

T ___ R ___

12) Port Sheldon

T ___ R ___

Township

T ___ R ___

2. Property Controlling in Section

S ___

T ___ R ___

S ___

T ___ R ___

3. Miscellaneous Property in Sec.

S ___

T ___ R ___

S ___

T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Randal J. Vugteveen, in a field survey on July 14, 1998

do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-3 GLO May 1832

Calvin Britian

Set Post

18" Beech N57°W 28 Links

7" White ASH 577°E 25 Links

Liber 1 Page 641 (J. Clapp 1972)

Found RR spike in Left Lane South Bound U.S.-31

Tel. Pole SW 51.05'

Tel. Pole SW 42.08'

St. Sign NE 62.14'

MSHD 1950± (Project 70-41, sheet #5)

1/8th Cor East 1323.50'

Centerline N Bound US 31 East 129.3'

MSHD angle between North line, Northeast 1/4, Section 12 and centerline alignment of US-31 to North = 115°08'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR Spike in Left Lane South Bound US-31

Iron in Monument Box at 1/8th cor N90°E 1322.93'

Centerline North Bound US-31 N90°E 130.94'

Measured angle between North line, Northeast 1/4,

Section 12 and centerline alignment of US-31 to

North = 115°07'08"

Accepted RR Spike as a careful and faithful

perpetuation of the position of the original corner.

Replaced RR spike with standard Ottawa County cap

on 3/4" X 24" iron bar.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" X 24" Iron Bar with Ottawa County Remon Cap

Set Nail and Remon Tag in W Side 8" Pine AZ = 25° 87.01'

Set Nail and Remon Tag in S side 8" Pine AZ = 44° 77.82'

Set Nail and Remon Tag in East side Power Pole AZ = 315° 117.05'

Southeast corner of a 4" X 6" Wood sign post AZ = 257° 101.48'

Southeast corner of a 4" X 6" Concrete Post AZ = 204° 122.43'

Centerline of Taylor Street AZ 0° 1.5'

Centerline of South Bound, US-31 pavement AZ 245° 7.0'

Signed by

Randal J. Vugteveen

Date

July 23, 1998

Surveyor's Michigan License No.

28429



\$9.00 CORNER
Receipt #13502