

# SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION

RECORDED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

94 DEC -8 PM 12:31

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

*Doris M. Kallman*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>16W</u>	<u>L-5 (S1/4 Cor Sec 12)</u>
	T _____ R _____	<u>Port Sheldon Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

John P. Clapp in a field survey on November 17, 1994 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

<p>L-5 Gov't Land Office Survey Notes May 1832 - Surveyor, Calvin Britain Post 8" Hemlock      S70°W 22 links 10" Hemlock     N33°E 4 links</p>	<p>L-5 Recorded in Liber 4, Page 325 June 10, 1982 Set steel bar midway on line between Section corners 8" Maple                      N                      40.15' 14" Maple                     NW                    49.91' 10" Maple                     NE                    61.02' 12" Tree                      SE                    18.31'</p>
---	--

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<p>L-5 Found capped steel bar and accepted it as a careful and faithful perpetuation of the position of the original corner Found Nail &amp; Tag in W Side 15" Maple Found Nail &amp; Tag in SW Side 18" Maple Found Scar in S Side 19" Maple Found Scar in SW Side 18" Tree</p>	<p>AZ. 10°      40.16' NW            49.90' AZ. 66°     61.18' ± AZ. 126°    18.39' ±</p>
--	---

P.A. 345 OTTAWA COUNTY  
PEER APPROVED 11/21/94

*Arden P. Nedwell*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>L-5 Set Ottawa County Remon Iron &amp; Cap O.C. Remon tag &amp; nail in SW Side 18" Tree O.C. Remon tag &amp; nail in N Side 26" Maple O.C. Remon tag &amp; nail in W Side 15" Maple O.C. Remon tag &amp; nail in S Side 19" Maple</p>	<p>AZ. 126°    18.42' AZ. 260°    35.91' AZ. 10°     40.21' AZ. 66°     61.19'</p>
---	--



Signed by John P. Clapp Date Nov 18, 1994

Surveyor's Michigan License No. 14091

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983