

**SURVEY &
REMONUMENTATION**

APR 05 1996

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

COMMISSION

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Ottawa
(County)

Located In: Corner Code #

1. Public Land Survey T6N R16W L-13
T R (S 1/4 cor. Sec.
T R 36, Port Sheldon
T R Twp.)

2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED
95 NOV 15 PM 2:14
Phyllis Ballman
REGISTER OF DEEDS
OTTAWA COUNTY, MI
Register of Deeds Stamp & File Number

I, Steven Lampen, in a field survey on October 23, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13
GLO Survey Notes No LCRC recorded
1832, Surveyor - Calvin Britain
set 1/2 mile post Old records of JKA, L-13 to K-13 2646.95'
4" Tamarack N 20° E 20 links L-13 to M-13 2645.02'
4" Tamarack N 44° W 36 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13
Found capped iron No. 23520 and is accepted as a careful and faithful perpetuation of the position of the original corner.
Measure L-13 to K-13 2647.17'
L-13 to M-13 2645.26'

PA. 345 OTTAWA COUNTY
PEER APPROVED 10/23/95

Medoy P. Medowald
DDY

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Ottawa County Remon. iron and cap in set monument box	AZ = MI State plane grid direction	
<u>L-13</u>	90° 34' 29"	
Remon. tag NW side 12" Maple	24° 14'	93.24'
"+" on bolt, N face concrete bridge	5° 48'	20.46'
"+" on bolt, N face concrete bridge	341° 14'	21.10'
"+" on bolt, S face concrete bridge	189° 18'	20.09'
"+" on bolt, S face concrete bridge	194° 04'	20.74'
Remon. tag SW side 10" Pine	142° 10'	94.78'
L-1 T5N R16W	90° 34' 29"	3.30'



Signed by Steven Lampen Date October 23, 1995

Surveyor's Michigan License No. 37279

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1976
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983