

**SURVEY & REMONUMENTATION**

APR 24 1995

COMMISSION

**OTTAWA COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 DEC 14 AM 9:43

*Polycarpus Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>16W</u>	<u>M-2 E 1/4 Cor.</u>
	T _____ R _____	<u>Sec 1</u>
	T _____ R _____	<u>Port Sheldon Twp.</u>
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, John P. Clapp, in a field survey on December 3, 19 94 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

M-2 Govt Land Office Survey Notes 1832-Surveyor, Calvin Britain Set Post 8" Beech            S51°W            7 links 24" Pine            N8°W            23 links	M-2 Recorded in Liber 2, Page 569 Sept 20, 1974 Set Cast Iron Monument 14" White Pine    E    3.70' 24" Oak            NE   32.37' 10" Oak            NW   19.45'
--	--

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

*Robert P. Hedwood* P.A. 345 OTTAWA COUNTY  
PEER APPROVED 12/12/94

M-2  
Found cast iron monument (top missing) and accepted it as a careful and faithful perpetuation of the position of the original corner  
Found Nail in N Side 16" White Pine            AZ 106°            4.57'  
Found Nail in SW Side 15" Oak            AZ 349°            19.63'  
Found Nail in SE Side 30" Oak            AZ 66°            33.42'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2  
Cast Iron Monument  
O.C Remon Tag & Nail in SSE Side 30" Oak    AZ.    66°            33.26'  
O.C. Remon Tag & Nail in E Side 17" Quad Oak    AZ.    354°            27.71'  
O.C. Remon Tag & Nail in N Side 14" White Pine    AZ.    287°            32.30'  
O.C. Remon Tag & Nail in NW Side 8" White Pine    AZ.    217°            98.21'

Signed by John P. Clapp *John P. Clapp*  
Surveyor's Michigan License No. 14091

Date Dec. 6, 1994

