

# SURVEY & REMONUMENTATION

APR 25 1995

OTTAWA COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 DEC -8 PM 12:31

COMMISSION

*Ruthie Robinson*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

For corners in  
Ottawa

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>16W</u>	M-4 (E1/4 Cor Sec 12) Port Sheldon Twp.
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

1. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 2. Private Claims \_\_\_\_\_

John P. Clapp, in a field survey on November 16, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	19	20	21	22	23	24				
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

1. Description of original monument and accessories and/or subsequent restoration:

<b>M-4</b> Gov't Land Office Survey Notes May 1832 - Surveyor, Calvin Britain Post 8" Pine S50°W 8 links 4" Pine N58°W 13 links	<b>M-4</b> Recorded in Liber 1, Page 647, Oct 13, 1972 Found Railroad Rail NE Cor Hse SW 109.54' SE Cor Hse NW 96.45' 18" Maple S 31.76' Pinched Pipe S 33.25' Power Pole SW 89.64'	<b>M-4</b> Recorded in Liber 5 Page 80, Dec 20, 1983 Set Cast Iron Monument 24" Maple S 32.98' Olive Twp Cor S 76.57' 6" Oak NE 54.12' Power Pole SW 90.07' Cor Blk Wall NW 35.05'
--	---	--

2. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

<b>M-4</b> Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner Found Pinched Pipe NE Corner of House SE Corner Concrete Block Wall Nail in Side of Power Pole Nail in Side of Power Pole Olive Twp Corner	AZ. 180° 33.17' AZ. 219° 109.49' AZ. 341° 35.06' AZ. 254° 89.63' AZ. 254° 90.09' AZ. 180° 76.63'
---	---

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

*Gregory D. Hedwood*

3. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<b>M-4</b> Ottawa County Cast Iron Monument O.C. Remon tag & nail in S Side Power Pole O.C. Remon tag & nail in ENE Side 13" Sassafras O.C. Remon tag & nail in NW Side 5" Oak O.C. Remon tag & nail in N Side 31" Oak	AZ. 254° 90.07' AZ. 309° 62.52' AZ. 44° 36.11' AZ. 112° 144.15'
---	--



Signed by John P. Clapp Date Nov. 17, 1994

Surveyor's Michigan License No. 14091

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983