

**SURVEY & REMONUMENTATION**

DEC 01 1993

**OTTAWA COUNTY REMONUMENTATION**

RECORDED

LAND CORNER RECORDATION CERTIFICATE 93 NOV 11 AM 11:56  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
For corners in

*Richard A. Williams*  
REGISTER OF DEEDS  
OTTAWA COUNTY, MI

| Ottawa (County)                    | Located In:              | Corner Code #              |
|------------------------------------|--------------------------|----------------------------|
| 1. Public Land Survey              | T <u>6N</u> R <u>16W</u> | <u>M-10 (E 1/4 Sec 25)</u> |
|                                    | T _____ R _____          | <u>Port Sheldon Twp.</u>   |
|                                    | T _____ R _____          | _____                      |
|                                    | T _____ R _____          | _____                      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____                      |
|                                    | S _____ T _____ R _____  | _____                      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____                      |
|                                    | S _____ T _____ R _____  | _____                      |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, David R. Greer, in a field survey on September 18, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

|  |   |   |
|--|---|---|
| Recorded in Liber 1 Page 413<br>May 26, 1972<br>M-10<br>Found 2" Iron Pipe<br>Set "T" Iron<br>30" Weeping Willow SW 92.30' | Recorded in Liber 1, Page 439<br>June 9, 1972<br>M-10<br>Set Cast Iron Monument<br>PP NE 205.30'<br>24" Willow SW 92.40'<br>18" Maple SSW 162.75' | Recorded in Liber 3, Page 360<br>July 3, 1979<br>M-10<br>Found Cast Iron Monument<br>30" Willow SW 92.30' |
|--|---|---|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-10  
Found steel bar which fits section line measurements from previous surveys made by Holland Engineering, Inc. when the corner was a cast iron monument ~~using this corner~~ and accepted it as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

|  |                     |
|--|---------------------|
| M-10<br>Replaced steel bar with O.C. Remonument Iron & Cap<br>AZ - Michigan State Grid Direction |                     |
| NE Cor. House Foundation   | AZ. 247°45' 212.69' |
| NW Cor. House Foundation   | AZ. 249°26' 230.19' |
| O.C. Remon. Tag & Nail in E Side 24" Maple   | AZ. 197°57' 164.06' |
| O.C. Remon. Tag & Nail in N Side Tri 4" Maple  | AZ. 291°33' 69.43'  |
| A-10 T6N R15W PK Nail in Washer  | AZ. 179°33' 28.30'  |



Signed by David R. Greer Date SEPT. 18, 1993  
Surveyor's Michigan License No. 16042

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983