

**SURVEY & REMONUMENTATION**

APR 25 1995

COMMISSION

OTTAWA COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
 94 DEC -8 PM 12:31

*Register of Deeds*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

or corners in

<u>Ottawa</u> (County)	Located In:	Corner Code #
Public Land Survey	T <u>6N</u> R <u>16W</u>	<u>M-12 (E 1/4 Cor. Sec 36)</u>
	T _____ R _____	<u>Port Sheldon Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

John P. Clapp in a field survey on November 14, 1994

I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

<b>M-12</b> Gov't Land Office Survey Notes May 1832 - Surveyor, Calvin Britain Post 26" Pine N87°W 26 links 4" Tamarack N15°W 19 links	<b>M-12</b> Recorded in Liber 4, Page 323, June 10, 1982 Found "T" Iron Olive Twp Cor S 17.80' Power Pole SW 85.99' 8" Pine SW 85.15' Pipeline Marker NW 31.27' C/L 144th Ave. E 41.00'	<b>M-12</b> Recorded in Liber 4 Page 337, Sept 24, 1982 Set Cast Iron Monument Pipeline Marker NW 31.26' Pipeline Marker SW 38.49' Pipe in S HDWL SE 30.65' Olive Twp. Cor. S 17.87'
---	---	---

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

P.A. 345 OTTAWA COUNTY

PEER APPROVED 11/21/94

<b>M-12</b> Found cast iron monument and accepted it as a careful and faithful perpetuation of the position of the original corner Found Nail & Tag in SE Side of 8" pine Found Nail & Tag in E Side of Power Pole Pipeline Marker Pipeline Marker Olive Corner C/L 144th Avenue	AZ. 236° 85.43' AZ. 198° 86.38' AZ. 323° 31.02' AZ. 222° 38.84' AZ. 180° 18.13' AZ. 90° 42.70'
---	---

*Handwritten signature: Rodney P. McDowell*

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<b>M-12</b> Found Ottawa County Cast Iron Monument O.C. Remon tag & nail in NW Face 9" Pine O.C. Remon tag & nail in WNW Face Power Pole O.C. Remon tag & nail in N Face 6" Pine Olive Township Corner	AZ. 236° 85.83' AZ. 198° 86.39' AZ. 111° 143.33' AZ. 180° 18.13'
---	---



Signed by John P. Clapp *[Signature]* Date Nov. 15, 1994  
 Surveyor's Michigan License No. 14091