SECTION

Surveyor's Michigan License No.

## OTTAWA COUNTY REMONUMENTATION

RECORDED

99 DEC -2 PM 1: 12

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in OTTAWA	· · · · · · · · · · · · · · · · · · ·	Sam Gentles
Located in:	Corner Code #	REGISTER OF DEEDS OTTAWA DELETY M
(County)		
1. Public Land Survey $T_{}^{6N}$	R	Deg. 2
2. Property Controlling ST in Section ST 3. Miscellaneous ST Property in Sec. ST	R	Register of Deeds Stamp & File Number
4. Lot No, Recorded Plat	·	ABCDEFGHIJKLM
5. Private Claims		1 3 5 5 5 1 3 3 3
Randal J. Vugteveen I,, in a field survey requirements of P.A. 74, Michigan P.A. of 1970, the conformance with regulations and rules therefore as re United States Department of the Interior, Bureau of Lithat the corner points mentioned in lines 3, 4 and 5 a Board of Land Surveyors or by a Decree of a Corecovered, found as expressed below:	equired in the current manual of survey instructions of and Management or by a decree of a Court of Law and above were in conformance with the rules of the Michig	e in 5   1/or 6   1/or 17   16   15   14   13   13   14   13   15   16   17   16   17   16   17   16   17   16   17   16   17   16   17   16   17   16   17   16   17   16   17   17
NOTE: Not more than 2 corners, all in the same on this certificate.	e town and range, may be recorded	9 10 30 29 28 27 26 25
×		11
A. Description of original monument and accel M-12 Peer Approved November 21, 1994 Liber 1, Page 432 (Clapp) Found Ottawa County Cast Iron Monument Nail & Remon Tag in NW face 9" Pine Az 236° 85.83' Nail & Remon Tag in WNW face Power Pole Az 198° 86.39' Nail & Remon Tag in N face 6" Pine Az 111° 143.33' Olive Township Comer Az 180° 18.13'  B. Description of corner evidence found and/		200 11 /15 /99 200 11 /15 /99
M-12 Corner Removed by Ottawa County Road Com		,
Found Nail & Remon Tag in NW side 12" Pine S56°W 85.83' Found Nail & Remon Tag in W side Power Pole S18°W 86.39' Found Nail & Remon Tag in N side 8" Pine S69°E 143.33'		ts a Set 3/4" X 36" Solid Bar with Ottawa Remon Cap at Intersection of witness ties.
C. Description of monument for corner and ac		e position of the corner:
M-12 3/4" X 36" Solid Bar with Ottawa County Remo	п Сар	
Found Nail and Remon Tag in NW side 12" Pine S56 Found Nail and Remon Tag in W side Power Pole S1 Found Nail and Remon Tag in N side 8" Pine S69°E Center Street sign N80°E 58.75' Centerline Pipleline Marker N35°W 31.11' N & S road East 43' E & W road South 21'	18°W 86.39'	NO. 20427
Signed by	//	Nov. 15, 1999