

**OTTAWA COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

97 JUL 24 PM 2:26

Phyllis Robinson
REGISTER OF DEEDS
OTTAWA COUNTY, MI

For corners in

Ottawa
(County)

Located In:

Corner Code #

- | | | | | | |
|------------------------------------|---|-----------|---|------------|----------------|
| 1. Public Land Survey | T | <u>7N</u> | R | <u>13W</u> | A-1 (NW, 6) |
| | T | _____ | R | _____ | Tallmadge Twp. |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | Common Corner |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Donald W. Schiele, in a field survey on March 11, 19 97, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

A-1 NW corner, Section 6, Tallmadge Twp. Original Government Corner Record: Corner post of Towns 7 & 8 North, Ranges 13 & 14 West Post Sugar 10 in dia bears S54W 10 lks dist Do 8 " " " N33W 34 " " John Mullett, Deputy Surveyor March 13, 1837	L.C.R.C. recorded in Liber 2, Page 379, 11-19-73 3/4" Pipe in pavement C/L street sign W 17.70' Trans. pole SW 102.60' Tel. pole SE 114.03'	L.C.R.C. recorded in Liber 3, Page 330, 1-11-79 Found 1" Round Iron by prev. witnesses SW to PP 102.63' SE to PP 114.4' W. to St. Sign 17.67'
--	---	---

(SEE REVERSE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-1 Found Cast Iron Monument inscribed "Section Corner", 2" below surface in Monument Box. and accepted as a careful and faithful perpetuation of the position of the original corner.

Found nail in SW side of Power Pole	S22°30'E	114.44'
Found nail & disk in NW side of Power Pole	S22°30'E	114.07'
Found nail in NE side of Power Pole	S24°W	102.64'
Westerly corner, concrete wingwall to House # 14430	N47°30'E	183.12' (E)
NW corner, foundation to House # 14376	S40°30'E	167.75' (E)
Fd. Ottawa County Remon Tag & nail in West side of Power Pole	S22°30'E	114.44'
Fd. Ottawa County Remon Tag & nail in East side of Power Pole	S24°W	103.03'
Fd. Ottawa County Remon Tag & nail in East side of Power Pole	N13°W	210.38'


Centerline asphalt road North & South, 8' East
On centerline gravel road to East
Field line to West, 18' South

P.A. 345 OTTAWA COUNTY
PEER APPROVED 4-21-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-1 Cast Iron Monument inscribed "Section Corner", 2" below surface in Monument Box.
Westerly corner, concrete wingwall to House # 14430
NW corner, foundation to House # 14376
Fd. Ottawa County Remon Tag & nail in West side of Power Pole
Fd. Ottawa County Remon Tag & nail in East side of Power Pole
Fd. Ottawa County Remon Tag & nail in East side of Power Pole
Centerline asphalt road North & South, 8' East
On centerline gravel road to East
Field line to West, 18' South

N47°30'E	183.12' (E)
S40°30'E	167.75' (E)
S22°30'E	114.44'
S24°W	103.03'
N13°W	210.38'



Signed by Donald W. Schiele
Surveyor's Michigan License No. 23517

Date March 15, 1997

Part A., continued:

L.C.R.C. recorded in Liber 6, Page 91, 1-28-91

A-1

Set CIM

3" Apple	WSW	35.22'
PP	SW	102.67'
PP	SE	114.45'
14" Elm	NW	58.78'

L.C.R.C. recorded in Liber 3, Page 392, 10-24-79

1A

Found 3/8" Iron

N45°W	Guy Pole	100.24'
S45°W	N. Line Pvmt	10.05'
S20°W	MBT Pole	110.90'

Note: This L.C.R.C. not correct location.
Refers to Section 1, T.7 N., R.13 W.

L.C.R.C. recorded in Remon Liber 2, Page 204, 12-15-94

M-13 (T8N, R14W)

Cast Iron Monument inscribed "Section Corner", 2" below surface in Monument Box.

Westerly corner, concrete wingwall to House # 14430	N47°30'E	183.12' (E)
NW corner, foundation to House # 14376	S40°30'E	167.75' (E)
Set Ottawa County Remon Tag & nail in West side of Power Pole	S22°30'E	114.44'
Set Ottawa County Remon Tag & nail in East side of Power Pole	S24°W	103.03'
Set Ottawa County Remon Tag & nail in East side of Power Pole	N13°W	210.38'

Centerline asphalt road North & South, 8' East
On centerline gravel road to East
Field line to West, 18' South