

APR 05 1996

Ottawa County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

95 DEC 12 PM 4:52

For corners in **COMMISSION**

<u>Ottawa</u> <small>(County)</small>	Located In:	Corner Code #:
1. Public Land Survey	T <u>T7N</u> R <u>R13W</u>	<u>A-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	<u>Common corner</u>
	S _____ T _____ R _____	<u>w/ M-3</u>
	S _____ T _____ R _____	<u>Allendale Twp</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

*Phyllis Robinson*  
 REGISTER OF DEEDS  
 OTTAWA COUNTY, MI

Register of Deeds Stamp & File Number

I, Maurice J. Rosema, in a field survey on Jan. 24, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

A-3	L.C.R.C. recorded in Liber	L.C.R.C. recorded in Liber
GLO - 1837 by	2, Page 689 - Oct. 22, 1974	2, Page 525 - July 9, 1974
John Mullett D.S.	(rec. as M-3, T7N, R14W)	(rec. as M-3, T7N, R14W)
Set post	3/4" steel bar in pav't	3/4" steel bar in pav't
12" Sugar S8 1/2°W 53 lks.	c/l st. sign SE 30.27'	c/l st. sign SE 30.27'
24" Sugar N46°W 6 lks.	MBT NW 40.96'	MBT NW 40.96'
	Fence cor. SW 38.50'	Fence cor. SW 38.50'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-3  
 Found C.I. mon. in mon. box

P.A. 345 OTTAWA COUNTY  
 PEER APPROVED 12/11/95

*Murray D. Rosema*  
 2071

I hereby accept this corner as a correct and accurate perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-3  
 C.I. mon. in mon. box

Set nail and O.C. tag in NE side P pole	S30°E 60.86'
Set nail and O.C. tag in NE side 26" Elm	S54°E 63.92'
Set nail and O.C. tag in SE side wood post	S20°W 110.10'
Center of stop sign	S37°E 40.36'
Set nail and O.C. tag in NE side P pole	N50°W 66.65'
Set nail and O.C. tag in S side 5" tw Maple	N80°E 85.86'



Signed by M. J. Rosema  
 Surveyor's Michigan License No. 27459

Date Oct. 21, 1995